

SECTION 10 11 00  
VISUAL DISPLAY CASE SURFACE  
Design Standard

PART 1 GENERAL

1.1 PURPOSE:

The ability to showcase items and information in public spaces in a safe and secure manner is critical in some locations within the college. The Display Cases must be aesthetically pleasing, integrate effectively with the building design, and offer a range of size options to fit the specific needs of the project.

PART 2 PRODUCT

The District has utilized a variety of manufacturer's products over the course of the Capital Improvement Program. While several brands may offer similar features, the District has selected a standard product: Platinum Visual Systems' Recessed Display Cases with Hinged Doors (HDS) and Trophy/Display Cases (SWS) units. Each unit should be specified with a color impregnated linoleum surface, which has demonstrated long life performance, and a pleasing visual for the space.

2.1 PLATINUM VISUAL RECESSED DISPLAY SPECIFICATIONS:

- A. Hinged doors with ¼" tempered glass and locks
- B. Continuous stainless steel piano hinges
- C. Birch veneer box, 12" deep
- D. Color impregnated linoleum tackable surface
- E. Aluminum Frame with 2" Face
- F. Available in 2 and 3 hinged door units, 4', 6' and 8' widths x 4' tall
- G. Adjustable ¼" tempered glass shelves
- H. Optional lights available
- I. Available to contractors through CollegeBuys program (CFCI)

Reference web site: <http://www.pvsusa.com/hds.html>

2.2 PLATINUM VISUAL TROPHY/DISPLAY CASES SPECIFICATIONS:

- A. Sliding doors with ¼" tempered glass, polished edges and locks
- B. Color impregnated linoleum tackable surface
- C. Aluminum Frame with 2" Face
- D. Available in 4', 6' and 8' widths x 4' tall x 1' deep
- E. Adjustable ¼" tempered glass shelves
- F. Optional lights available
- G. Optional base and cornice available

H. Available to contractors through CollegeBuys program (CFCI)

Reference web site: <http://www.pvsusa.com/sws.html>

### 2.3 APPROVED COLORS AND FINISHES

Color Impregnated Tack Board – all colleges and district office:

- A. 15 Platinum
- B. 11 Buff
- C. 21 Steel Gray

### 2.4 FABRIC WRAPPED TACK & ACOUSTICAL PANELS

A. Cañada College

- 1. Maharam Parallel Cadet 901180-011
- 2. Maharam Parallel Boa 901180-010
- 3. Maharam Parallel Ochre 901180-009
- 4. Maharam Parallel Fog 901180-003

B. College of San Mateo

- 1. Maharam Silk Brush Pebble 304701-015
- 2. Maharam Silk Brush Champagne 304701-067
- 3. Maharam Silk Brush Hay 304701-068

C. Skyline College

- 1. Maharam Mettle Silica 398230 004
- 2. Maharam Mettle Paraffin 398230 005
- 3. Maharam Mettle Malt 398230 006

## PART 3 EXECUTION

### 3.1 SUBSTITUTIONS ALLOWED?

- A. No substitute to this device descriptor protocol is allowed.

END OF SECTION