

ABBREVIATIONS

∅	CENTERLINE	(N)	NEW
∠	DIAMETER OR ROUND	N.I.C.	NOT IN CONTRACT
ACC.	ACCESSIBLE	NO. OF #	NUMBER
ACOUS.	ACOUSTICAL	NOM.	NOMINAL
ADJ.	ADJUSTABLE	N.T.S.	NOT TO SCALE
AGG.	AGGREGATE	O/	OVER
AL.	ALUMINUM	O.A.	OVERALL
APPROX.	APPROXIMATE	O.C.	ON CENTER
ARCH.	ARCHITECTURAL	O.D.	OUTSIDE DIAMETER
A.P.L.	ASSUMED PROPERTY LINE	OPF.	OPPOSITE
A.F.F.	ABOVE FINISH FLOOR	O.F.D.	OVERFLOW DRAIN
ADD.	ADDITIONAL	PEN.	PENETRATIONS
		PL.	PLATE
BD.	BOARD	PLAM.	PLASTIC LAMINATE
BITUM.	BITUMINOUS	PLYWD.	PLYWOOD
BLDG.	BUILDING	FR.	FAIR
BLKG.	BLOCKING	FPD.	PAPER TOWEL DISPENSER
BM.	BEAM	F.A.D.	POURED-IN-PLACE
BOT.	BOTTOM	F.I.P.	POURED-IN-PLACE
		P.T.	PRESSURE TREATED
CAB.	CABINET	G.T.	GRAVEL
C.B.	CATCH BASIN	R.	RISER
C.T.	CERAMIC TILE	RAD.	RADIUS
C.C.T.	CUBICLE CURTAIN TRACK	R.D.	ROOF DRAIN
C.I.	CAST IRON	REF.	REFERENCE
CLG.	CEILING	REFR.	REFRIGERATOR
CLR.	CLEAR	REINF.	REINFORCED
COL.	COLUMN	REQD.	REQUIRED
CONC.	CONCRETE	RESIL.	RESILIENT
CONT.	CONTINUOUS	R.H.	ROBE HOOK
CORR.	CORRIDOR	RM.	ROOM
CTSK.	COUNTERSINK	R.O.	ROUGH OPENING
C.M.U.	CONCRETE MASONRY	RT.	RESILIENT TILE
C.D.U.	COMBINATION DISPENSING UNIT	RND.	REDWOOD
		R.W.L.	RAIN WATER LEADER
		S.C.	SOLID CORE
DBL.	DOUBLE	SCH.	SCHEDULE
DEPT.	DEPARTMENT	SD.	SOAP DISPENSER
D.F.	DRINKING FOUNTAIN	SECT.	SECTION
DET.	DETAIL	SH.	SHELF
DIA.	DIAMETER	SHWR.	SHOWER
DIM.	DIMENSION	SHT.	SHEET
DISP.	DISPENSER	SIM.	SIMILAR
DN.	DOWN	S.M.S.	SHEET METAL SCREW
DR.	DOOR	SND.	SANITARY NAPKIN DISPOSAL
DS.	DOWNSPOUT	SNV.	SANITARY NAPKIN VENDOR
DWG.	DRAWING	SSD.	SEE STRUCTURAL DRAWINGS
D.D.	DECK DRAIN	STD.	STANDARD
D.F.	DOUGLAS FIR	STL.	STEEL
		STOR.	STORAGE
(E)	EXISTING	STR.	STRUCTURAL
EA.	EACH	SUSP.	SUSPENDED
E.L.	EXPANSION JOINT	TGD.	TOILET SEAT COVER DISPENSER
EL.	ELEVATION	T.D.	TRENCH DRAIN
ELEC.	ELECTRICAL	TRD.	TREAD
ELEV.	ELEVATOR	T.B.	TOWEL BAR
EMERG.	EMERGENCY	T.O.C.	TOP OF CURB/CONCRETE
ENCL.	ENCLOSURE	TEL.	TELEPHONE
EQ.	EQUAL	TER.	TERRAZZO
EQPT.	EQUIPMENT	T.G.	TONGUE AND GROOVE
E.W.C.	ELECTRIC WATER COOLER	THK.	THICK
EXP.	EXPANSION	TKBD.	TACKBOARD
EXT.	EXTERIOR	T.P.	TOP OF PAVEMENT/TELEPHONE PANELBOARD
		TPD.	TOILET PAPER DISPENSER
F.A.	FIRE ALARM	T.V.	TELEVISION
F.O.A.	FLOOR CLEAN OUT	TYP.	TYPICAL
F.D.	FLOOR DRAIN	T.O.S.	TOP OF STEEL
FDN.	FOUNDATION	T.O.W.	TOP OF WALL
F.E.	FIRE EXTINGUISHER	U.O.N.	UNLESS OTHERWISE NOTED
F.E.C.	FIRE EXTINGUISHER CAB.	VGT.	VINYL COMPOSITION TILE
F.H.C.	FIRE HOSE CABINET	VDB.	VISUAL DISPLAY BOARD
FIN.	FINISH	VERT.	VERTICAL
FL.	FLOOR	VEST.	VESTIBULE
FLUOR.	FLUORESCENT	W/	WITH
F.O.C.	FACE OF CONCRETE	W.C.	WATER CLOSET
F.O.F.	FACE OF FINISH	W.D.	WOOD
F.O.S.	FACE OF STUDS	W/O	WITHOUT
F.S.S.	FOLDING SHOWER SEAT	WP.	WATERPROOF
FT.	FOOT OR FEET	WR.	WASTE RECEPTACLE
FTS.	FOOTING	WT.	WEIGHT
FURR.	FURRING		
F.H.S.	FLAT HEAD SCREW		
F.R.	FIRE RETARDANT		
GA.	GAGE		
GALV.	GALVANIZED		
GL.	GLASS		
GND.	GROUND		
GYP.	GYPSPUM		
G.W.B.	GYPSPUM WALL BOARD		
GEN.	GENERAL		
H.B.	HOSE BIB		
H.C.	HOLLOW CORE		
H.M.	HOLLOW METAL		
HORIZ.	HORIZONTAL		
HR.	HOUR		
I.D.	INSIDE DIAMETER		
INSUL.	INSULATION		
INT.	INTERIOR		
IVT.	INTRAVENOUS TRACK		
JAN.	JANITOR		
J.T.	JOINT		
KIT.	KITCHEN		
LAB.	LABORATORY		
LAM.	LAMINATE		
LAV.	LAVATORY		
LT.	LIGHT		
MAT.	MATERIAL		
MAX.	MAXIMUM		
M.C.	MEDICINE CABINET		
MECH.	MECHANICAL		
MEMB.	MEMBRANE		
MET.	METAL		
MFR.	MANUFACTURER		
MIN.	MINIMUM		
M.	MIRROR (FRAMED)		
MISC.	MISCELLANEOUS		
M.O.	MASONRY OPENING		
MTD.	MOUNTED		
ML.	MULLION		
MG.	MEDICAL GAS PANEL		
M.B.	MACHINE BOLT		
MK.	MARKER BOARD		
MBH.	MOP AND BROOM HOLDER		

GRAPHIC SYMBOLS

- GRAPHIC SYMBOLS REPRESENT OBJECTS, ELEMENTS, EQUIPMENT, INSTRUCTIONS, LOCATION, CONVENTIONS, ETC. THEY DO NOT REPRESENT THE SHAPE, SIZE, DIMENSION OF THE ACTUAL OBJECT.
- EACH DRAWING GROUP (IE MECHANICAL, ELECTRICAL) HAS ITS OWN SYMBOLS, ABBREVIATIONS, LEGEND AND NOTES. THE INFORMATION AND SYMBOLS ON THIS DRAWING ARE GENERAL AND APPLY TO ALL DRAWINGS.

GENERAL SYMBOLS

	DOOR SYMBOL (LETTER DESIGNATES NUMBER OF DOOR IN ROOM) SEE A.S.O FOR DOOR SCHEDULE
	WINDOW TYPE (LETTER DESIGNATES NUMBER OF WINDOW IN ROOM) SEE A.S.O FOR WINDOW SCHEDULE
	EQUIPMENT SYMBOL
	REVISION
	MATCH LINE (SHADED PORTION IS THE SIDE CONSIDERED)
	WORK POINT, CONTROL POINT OR DATUM POINT
	SECTION IDENTIFICATION SHEET WHERE SECTION IS DRAWN
	DETAIL IDENTIFICATION SHEET WHERE DETAIL IS DRAWN
	INTERIOR ELEVATIONS (SOLID ARROW INDICATES ELEVATION DRAWN) SHEET WHERE ELEVATION IS DRAWN
	WAITING ROOM
	DIMENSION LINES
	ALIGN (FIN. FACE TO FIN. FACE)
	LIMIT OF WORK

PARTITIONS

	EXISTING WALL OR PARTITION TO REMAIN
	EXISTING WALL OR PARTITION TO BE REMOVED
	NEW PARTITIONS
	EXISTING DOORS TO REMAIN
	EXISTING DOOR TO BE REMOVED
	NEW DOORS (FLOOR FINISH TRANSITION WHERE INDICATED AT CENTER LINE OF DOOR, TYPICAL)
	EXISTING WINDOW TO REMAIN
	EXISTING WINDOW TO BE REMOVED
	NEW WINDOW (REFER TO SCHEDULE IN SPECIFICATIONS SECTION 08005)
	CHASE WALL (PIPE OR PLUMBING)

EQUIPMENT

	ROBE HOOK
	CLOCK
	FIRE EXTINGUISHER CABINET
	HANDRAIL / WALL PROTECTION
	VISUAL DISPLAY BOARDS
	EMERGENCY EYEWASH / SHOWER
	CORNER GUARD
	EDGE GUARD

CASEWORK

	WALL HANGING CABINETS OR SHELVES
	BASE CABINET COUNTER TOP
	OWNER FURNISHED ITEMS (NOT IN CONTRACT)

PLUMBING

	WALL MOUNTED TOILET
	FLOOR MOUNTED TOILET
	FLOOR CLEAN OUT (FCO) (SEE PLUMBING PLANS FOR LOCATIONS) (N) INDICATES NEW FCO (E) INDICATES EXISTING FCO
	FLOOR SINK (PROVIDE COVER WHERE EXPOSED TO FOOT TRAFFIC)

MECHANICAL

	SUPPLY DIFFUSER
	RETURN AIR GRILLE
	EXHAUST GRILLE

ELECTRICAL

	2' X 4' LIGHT FIXTURE
	2' X 2' LIGHT FIXTURE
	RECESSED DOWNLIGHT
	STRIP LIGHTING FIXTURE
	EXIT SIGN
	SMOKE DETECTOR
	TELEVISION AND BRACKET
	SPEAKER

Sugimura & Associates Architects
 Architecture • Interiors
 Landscape Architecture
 2155 South Bascom Ave., Suite 200
 Campbell, CA 95008
 408-879-0600 Fax 408-377-6066
 COPYRIGHT © 2003 Sugimura & Associates Architects



REVISIONS

NO.	ITEM	DATE
1	CONSTRUCTION ISSUE 6/10/04	
2	CONFORM SET	4/4/04

ABBREVIATIONS & SYMBOLS
 SKYLINE COLLEGE SWING SPACE
 PERMIT PACKAGE #3
 SKYLINE COLLEGE
 3300 COLLEGE DRIVE
 SAN BRUNO, CA 94066

CLIENT APPROVAL:

DRAWN BY: KH
 CHECKED BY: MDN
 JOB NO: 2145.002
 DATE: 13 FEB 2004