CHILLED WATER AIR HANDLING UNIT SCHEDULE

NO.	MANUF. & MODEL#	SUPPLY CFM	EXH CFM	SUPPLY FAN ESP	SUPPLY FAN BHP	SUPPLY FAN HP	SUPPLY FAN RPM	EXHAUST FAN ESP	EXHAUST FAN BHP	EXHAUST FAN HP	EXHAUST FAN RPM	COOLING VALVE DATA Cv	COOLING VALVE DATA SIZE	COOLING VALVE DATA 2W/3W	COOLING VALVE DATA S.O.H	COOLING COIL DATA EADB	EAWB	LADB	LAWB	APD	CAP.	SENS.	EWT	LWT	GPM	WPD
AHU 1	SCOTT SPRINGFIELD	45000	45000	2.0	-	50	1200	1.25	-	30	1750	170	4"	2-WAY	40 PSI	88.0	66.0	53.1	51.9	0.71	1846	1064	42°F	60°F	206	8.5
AHU 2	SCOTT SPRINGFIELD	45000	45000	2.0	-	50	1200	1.25	-	30	1750	170	4"	2-WAY	40 PSI	88.0	66.0	53.1	51.9	0.71	1846	1064	42°F	60°F	206	8.5

NO.	HEAT RECOVERY-SUPPLY SIDE- EADB	LADB	APD	SENS.	EWT	LWT	GPM	WPD	HEAT RECOVERY-EXHAUST SIDE- EADB	LADB	APD	SENS.	EWT	LWT	GPM	WPD	FILTER DATA PRE-FILTERS	FINAL-FILTER	ELECTRICAL DATA V-Φ-HZ	MCA	MOCP	OPER. WGT.	REMARKS
AHU 1	35.0	55.3	0.21	637.0	59.0	50.0	141.4	4.99	74.0	53.8	0.19	585.8	50.0	59.1	141.4	4.99	2"-30% PLEATED	12"-85% CARTRIDGE	460-3Φ-60	MCA	MOCP	26000	PREMIUM EFFICIENCY INVERTER DUTY FAN MOTOR WITH VFD FOR SUPPLY AND EXHAUST, 2" INTERNAL ISOLATION WITH SEISMIC RESTRAINTS, STAINLESS STEEL IAQ DRAIN PAN, COPPER TUBE & COPPER FIN COILS, PERFORATED DOUBLE WALL CONSTRUCTION.
AHU 2	35.0	55.3	0.21	637.0	59.0	50.0	141.4	4.99	74.0	53.8	0.19	585.8	50.0	59.1	141.4	4.99	2"-30% PLEATED	12"-85% CARTRIDGE	460-3Φ-60	MCA	MOCP	26000	PREMIUM EFFICIENCY INVERTER DUTY FAN MOTOR WITH VFD FOR SUPPLY AND EXHAUST, 2" INTERNAL ISOLATION WITH SEISMIC RESTRAINTS, STAINLESS STEEL IAQ DRAIN PAN, COPPER TUBE & COPPER FIN COILS, PERFORATED DOUBLE WALL CONSTRUCTION.

VAV BOX SCHEDULE

NO.	MANUFACTURER & MODEL NO.	SERVICE	BOX SIZE	COOLING CFM MAX	COOLING CFM MIN	HEATING CFM MAX	HEATING CFM MIN	AIR T.P.D.	HOT WATER REHEAT COIL EAT (°F)	LAT (°F)	CAPACITY (MBH)	EWT (°F)	LWT (°F)	GPM	ROWS	H2O T.P.D.	CONTROL VALVE TYPE	SIZE	Cv	REMARKS
VAV 1-1-1	TITUS ESV	1ST FLR MAIN LOBBY	16	2075	480	480	480	0.32	45	75.8	16.0	180	140	0.8	2	0.1	2-WAY	1/2"	0.8	YAMAS CONTROLLER
VAV 1-1-2	TITUS ESV	WOMENS LOCKER/SHOWER	16	1530	1530	1530	1530	0.32	45	70.0	41.3	180	140	2.1	2	0.2	2-WAY	1/2"	1.9	YAMAS CONTROLLER
VAV 1-1-3	TITUS ESV	LOBBY	16	2000	580	580	580	0.55	45	94.5	31.0	180	140	1.6	2	0.1	2-WAY	1/2"	1.2	YAMAS CONTROLLER
VAV 1-1-4	TITUS ESV	MENS LOCKER/SHOWER	14	1365	1365	1365	1365	0.42	45	70.0	36.9	180	140	1.8	2	0.4	2-WAY	1/2"	1.9	YAMAS CONTROLLER
VAV 1-2-5	TITUS ESV	CLASSROOM 280	20	2400	720	1400	720	0.23	45	78.4	50.5	180	140	2.5	2	0.1	2-WAY	1/2"	1.9	YAMAS CONTROLLER
VAV 1-2-6	TITUS ESV	ESTHETICS	14	1350	450	450	450	0.41	45	77.4	15.7	180	140	0.8	2	0.2	2-WAY	1/2"	0.8	YAMAS CONTROLLER
VAV 1-2-7	TITUS ESV	2ND FLR LOBBY	14	1600	450	450	450	0.58	45	95.7	24.6	180	140	1.2	2	0.1	2-WAY	1/2"	1.2	YAMAS CONTROLLER
VAV 1-2-8	TITUS ESV	COSMETOLOGY WAITING	8	430	195	195	195	0.37	45	80.8	7.5	180	140	0.4	2	0.1	2-WAY	1/2"	0.3	YAMAS CONTROLLER
VAV 1-2-9	TITUS ESV	2ND FLR OFFICES	8	390	145	145	145	0.31	45	83.0	6.0	180	140	0.3	2	0.1	2-WAY	1/2"	0.3	YAMAS CONTROLLER
VAV 1-2-10	TITUS ESV	SPINNING	16	2000	580	580	580	0.55	45	76.3	19.6	180	140	1.0	2	0.1	2-WAY	1/2"	0.8	YAMAS CONTROLLER
VAV 1-2-11	TITUS ESV	GROUP EXERCISE	14	1200	450	450	450	0.32	45	83.8	18.9	180	140	0.9	2	0.1	2-WAY	1/2"	0.8	YAMAS CONTROLLER
VAV 1-2-12	TITUS ESV	YOGA	16	1980	580	580	580	0.54	45	84.9	25.0	180	140	1.3	2	0.1	2-WAY	1/2"	1.2	YAMAS CONTROLLER
VAV 1-2-13	TITUS ESV	PILATES	14	1320	400	400	400	0.39	45	78.1	16.1	180	140	0.8	2	0.1	2-WAY	1/2"	0.8	YAMAS CONTROLLER
VAV 1-2-14	TITUS ESV	2ND FLR LOBBY	12	1075	325	325	325	0.50	45	89.1	15.5	180	140	0.8	2	0.1	2-WAY	1/2"	0.8	YAMAS CONTROLLER
VAV 1-2-15	TITUS ESV	MENS/WOMENS RESTROOMS	12	1000	325	325	325	0.43	45	70.0	8.8	180	140	0.4	2	0.1	2-WAY	1/2"	0.3	YAMAS CONTROLLER
VAV 1-3-16	TITUS ESV	ASSISTING TREATMENT	12	1100	325	325	325	0.52	45	89.5	15.6	180	140	0.8	2	0.1	2-WAY	1/2"	0.8	YAMAS CONTROLLER
VAV 1-3-17	TITUS ESV	HYGENE TREATMENT	20	2200	585	585	585	0.20	45	89.9	28.4	180	140	1.4	2	0.1	2-WAY	1/2"	1.2	YAMAS CONTROLLER
VAV 1-3-18	TITUS ESV	3RD FLR OFFICES	8	550	145	145	145	0.61	45	99.9	8.6	180	140	0.4	2	0.1	2-WAY	1/2"	0.3	YAMAS CONTROLLER
VAV 1-3-19	TITUS ESV	RADIOLOGY	12	950	325	325	325	0.39	45	77.5	11.4	180	140	0.6	2	0.1	2-WAY	1/2"	0.46	YAMAS CONTROLLER
VAV 1-3-20	TITUS ESV	STERILIZATION	10	715	230	230	230	0.44	45	88.4	10.8	180	140	0.5	2	0.1	2-WAY	1/2"	0.46	YAMAS CONTROLLER
VAV 1-3-21	TITUS ESV	STUDENT LOUNGE	12	1100	340	340	340	0.52	45	91.9	17.2	180	140	0.9	2	0.1	2-WAY	1/2"	0.8	YAMAS CONTROLLER
VAV 1-3-22	TITUS ESV	FACULTY ROOM	12	900	325	325	325	0.35	45	79.2	12.0	180	140	0.6	2	0.1	2-WAY	1/2"	0.46	YAMAS CONTROLLER
VAV 1-3-23	TITUS ESV	OFFICES	10	700	230	230	230	0.43	45	87.4	10.5	180	140	0.5	2	0.1	2-WAY	1/2"	0.46	YAMAS CONTROLLER
VAV 1-3-24	TITUS ESV	MEETING ROOM	12	1000	310	375	310	0.43	45	82.1	15.0	180	140	0.8	2	0.1	2-WAY	1/2"	0.8	YAMAS CONTROLLER
VAV 1-3-25	TITUS ESV	MEETING ROOM	12	880	300	325	300	0.34	45	86.1	14.4	180	140	0.7	2	0.1	2-WAY	1/2"	0.8	YAMAS CONTROLLER
VAV 1-3-26	TITUS ESV	OFFICES	10	580	300	530	300	0.29	45	78.6	19.2	180	140	1.0	2	0.1	2-WAY	1/2"	0.8	YAMAS CONTROLLER
VAV 1-3-27	TITUS ESV	OFFICES	10	580	230	230	230	0.29	45	91.7	11.6	180	140	0.6	2	0.1	2-WAY	1/2"	0.46	YAMAS CONTROLLER
VAV 1-3-28	TITUS ESV	3RD FLR LOBBY	16	2000	580	580	580	0.55	45	83.2	23.9	180	140	1.2	2	0.1	2-WAY	1/2"	1.2	YAMAS CONTROLLER
VAV 1-3-29	TITUS ESV	MENS/WOMENS RESTROOMS	12	800	360	360	360	0.28	45	82.9	14.8	180	140	0.7	2	0.1	2-WAY	1/2"	0.8	YAMAS CONTROLLER
VAV 1-3-30	TITUS ESV	DENTAL LAB	14	1200	450	450	450	0.32	45	74.2	14.2	180	140	0.7	2	0.1	2-WAY	1/2"	0.46	YAMAS CONTROLLER
VAV 1-3-31	TITUS ESV	DENTAL WAITING	10	500	230	230	230	0.32	45	82.1	14.2	180	140	0.5	2	0.1	2-WAY	1/2"	0.46	YAMAS CONTROLLER

VAV BOX SCHEDULE

NO.	MANUFACTURER & MODEL NO.	SERVICE	BOX SIZE	COOLING CFM MAX	COOLING CFM MIN	HEATING CFM MAX	HEATING CFM MIN	AIR T.P.D.	HOT WATER REHEAT COIL EAT (°F)	LAT (°F)	CAPACITY (MBH)	EWT (°F)	LWT (°F)	GPM	ROWS	H2O T.P.D.	CONTROL VALVE TYPE	SIZE	Cv	REMARKS
VAV 2-1-1	TITUS ESV	CARDIO TRAINING	20	3000	1150	1400	1150	0.36	45	74.4	44.5	180	140	2.2	2	0.3	2-WAY	1/2"	1.9	YAMAS CONTROLLER
VAV 2-1-2	TITUS ESV	CARDIO TRAINING	20	3000	1250	1400	1250	0.36	45	76.0	46.8	180	140	2.3	2	0.3	2-WAY	1/2"	1.9	YAMAS CONTROLLER
VAV 2-1-3	TITUS ESV	ADAPTED PE EXERCISE	20	2110	700	1400	700	0.18	45	75.9	46.7	180	140	2.3	2	0.3	2-WAY	1/2"	1.9	YAMAS CONTROLLER
VAV 2-1-4	TITUS ESV	STRENGTH TRAINING	20	3000	960	1400	700	0.36	45	75.1	45.5	180	140	2.3	2	0.3	2-WAY	1/2"	1.9	YAMAS CONTROLLER
VAV 2-1-5	TITUS ESV	LOUNGE	6	250	150	150	150	0.37	45	70.0	4.1	180	140	0.2	2	0.1	2-WAY	1/2"	0.3	YAMAS CONTROLLER
VAV 2-1-6	TITUS ESV	DEAN/ WELLNESS	14	1500	450	450	450	0.51	45	85.8	19.8	180	140	1.0	2	0.1	2-WAY	1/2"	0.8	YAMAS CONTROLLER
VAV 2-1-7	TITUS ESV	STAFF LOUNGE	10	635	145	145	145	0.3	45	70.0	3.9	180	140	0.2	2	0.1	2-WAY	1/2"	0.3	YAMAS CONTROLLER
VAV 2-2-8	TITUS ESV	SENIOR LAB	20	3600	1080	1400	1080	0.52	45	74.4	44.5	180	140	2.2	2	0.3	2-WAY	1/2"	1.9	YAMAS CONTROLLER
VAV 2-2-9	TITUS ESV	SENIOR LAB	20	3600	1080	1400	1080	0.52	45	73.3	42.8	180	140	2.1	2	0.3	2-WAY	1/2"	1.9	YAMAS CONTROLLER
VAV 2-2-10	TITUS ESV	DISPENSARY/ LAUNDRY	10	700	370	370	370	0.43	45	70.0	10.0	180	140	0.5	2	0.1	2-WAY	1/2"	0.46	YAMAS CONTROLLER
VAV 2-2-11	TITUS ESV	FRESHMAN LAB	20	3600	1080	1400	1080	0.52	45	76.1	47.0	180	140	2.4	2	0.3	2-WAY	1/2"	1.9	YAMAS CONTROLLER
VAV 2-2-12	TITUS ESV	CLASSROOM 210	14	1200	390	450	390	0.32	45	86.3	20.1	180	140	1.0	2	0.1	2-WAY	1/2"	0.8	YAMAS CONTROLLER
VAV 2-2-13	TITUS ESV	2ND FLR OFFICES	10	520	230	230	230	0.24	45	70.0	6.2	180	140	0.3	2	0.1	2-WAY	1/2"	0.3	YAMAS CONTROLLER
VAV 2-2-14	TITUS ESV	CORRIDOR 240B	14	1400	420	420	420	0.44	45	91.7	22.7	180	140	1.1	2	0.2	2-WAY	1/2"	0.8	YAMAS CONTROLLER
VAV 2-2-15	TITUS ESV	CENTRAL COPY	8	305	145	145	145	0.19	45	70.0	39.2	180	140	0.2	2	0.1	2-WAY	1/2"	0.3	YAMAS CONTROLLER
VAV 2-3-16	TITUS ESV	CLASSROOM 355	14	1200	420	420	420	0.32	45	78.6	16.4	180	140	0.8	2	0.1	2-WAY	1/2"	0.8	YAMAS CONTROLLER
VAV 2-3-17	TITUS ESV	CLASSROOM 357	14	1400	470	470	470	0.44	45	81.9	18.7	180	140	0.9	2	0.1	2-WAY	1/2"	0.8	YAMAS CONTROLLER
VAV 2-3-18	TITUS ESV	NURSING SKILLS LAB	10	550	230	230	230	0.26	45	74.8	7.4	180	140	0.4	2	0.1	2-WAY	1/2"	0.3	YAMAS CONTROLLER
VAV 2-3-19	TITUS ESV	NURSING SKILLS LAB	10	590	230	230	230	0.30	45	75.3	7.5	180	140	0.4	2	0.1	2-WAY	1/2"	0.3	YAMAS CONTROLLER
VAV 2-3-20	TITUS ESV	NURSING SKILLS LAB	14	1400	450	450	450	0.44	45	94.0	23.8	180	140	1.2	2	0.2	2-WAY	1/2"	0.8	YAMAS CONTROLLER
VAV 2-3-21	TITUS ESV	NURSING SKILLS LAB	12	1090	350	350	350	0.51	45	80.8	13.5	180	140	0.7	2	0.1	2-WAY	1/2"	0.46	YAMAS CONTROLLER
VAV 2-3-22	TITUS ESV	NURSING SKILLS LAB	6	270	80	80	80	0.43	45	93.6	4.2	180	140	0.2	2	0.1	2-WAY	1/2"	0.3	YAMAS CONTROLLER
VAV 2-3-23	TITUS ESV	NURSING SKILLS LAB	6	190	80	80	80	0.21	45	82.5	3.2	180	140	0.2	2	0.1	2-WAY	1/2"	0.3	YAMAS CONTROLLER
VAV 2-3-24	TITUS ESV	CLASSROOM 390	14	1800	450	450	450	0.73	45	89.3	21.5	180	140	1.1	2	0.1	2-WAY	1/2"	0.8	YAMAS CONTROLLER
VAV 2-3-25	TITUS ESV	3RD FLR OFFICES	8	480	300	350	300	0.47	45	74.1	11.0	180	140	0.6	2	0.1	2-WAY	1/2"	0.46	YAMAS CONTROLLER
VAV 2-3-26	TITUS ESV	CORRIDOR	14	1600	480	1600	480	0.58	45	76.7	54.7	180	140	2.7	2	0.9	2-WAY	1/2"	1.9	YAMAS CONTROLLER
VAV 2-3-27	TITUS ESV	OFFICES	8	460	300	300	300	0.43	45	73.1	14.0	180	140	0.7	2	0.1	2-WAY	1/2"	0.8	YAMAS CONTROLLER

PUMP SCHEDULE

NO.	MANUFACTURER & MODEL NO.	SERVICE	TYPE	GPM	HEAD FT.	NPSH	RPM	BHP	HP	VOLTAGE	OPER. WGT. LBS.	REMARKS
CHWP 1	BELL & GOSSETT SERIES 1510 3BC	AHU-1 COOLING	END SUCTION	450	60	-	1750	8.62	10	460V 3Φ/60Hz	370	PREMIUM EFFICIENCY INVERTER DUTY RATED ODP MOTOR, SUCTION DIFFUSER W/STRAINER.
CHWP 2	BELL & GOSSETT SERIES 1510 3BC	AHU-2 COOLING	END SUCTION	450	60	-	1750	8.62	10	460V 3Φ/60Hz	370	PREMIUM EFFICIENCY INVERTER DUTY RATED ODP MOTOR, SUCTION DIFFUSER W/ STRAINER -STANDBY-
HWP 1	BELL & GOSSETT SERIES 80 1½X1½X9½	BLDG. HEATING	IN-LINE	75	80	-	1750	2.75	5	460V 3Φ/60Hz	190	PREMIUM EFFICIENCY INVERTER DUTY RATED ODP MOTOR.
HWP 2	BELL & GOSSETT SERIES 80 1½X1½X9½	BLDG HEATING	IN-LINE	75	80	-	1750	2.75	5	460V 3Φ/60Hz	190	PREMIUM EFFICIENCY INVERTER DUTY RATED ODP MOTOR. -STANDBY-
RAP 1	BELL & GOSSETT SERIES 80 3X3X9½B	HEAT RECOVERY	IN-LINE	150	20	-	1150	1.15	1.5	460V 3Φ/60Hz	175	PREMIUM EFFICIENCY INVERTER DUTY RATED TEFC MOTOR.
RAP 2	BELL & GOSSETT SERIES 80 3X3X9½B	HEAT RECOVERY	IN-LINE	150	20	-	1150	1.15	1.5	460V 3Φ/60Hz	175	PREMIUM EFFICIENCY INVERTER DUTY RATED TEFC MOTOR.

CHILLED WATER FAN COIL UNIT SCHEDULE

NO.	MANUFACTURER & MODEL NO.	COOLING CAP. (MBH) TOTAL	SENS.	E.A.T. (°F) Db / Wb	L.A.T. (°F) Db / Wb	FAN DATA CFM	TSP	RPM	COOLING COIL DATA ROWS	E.W.T.	L.W.T.	GPM	P.D.	CONTROL VALVE Cv	SIZE	2"-20% FILTER (NO.) - H x W	HP	VOLTAGE V/PH/HZ.	OPER. WT. LBS.	REMARKS
FC 1	TRANE BCHC 072	61000	61000	80/67	54/53	2400	1.5	979	4	44	56	16.1	7.9	14	1" 3-WAY	(1) 20x20 (1) 20x25	1	460V/3Φ	300	HIGH CAP COIL, LH COIL CONNECTION

VARIABLE FREQUENCY DRIVE SCHEDULE

NO.	MANUFACTURER & MODEL NO.	SERVICE	HP	EFF	TEMPERATURE MAX	TEMPERATURE MIN	LOCATION	ELECTRICAL	OPER. WGT. LBS.	REMARKS
VFD 1	ABB ACH-550	CHWP-1	10	97	104	32	MECH. RM	460V/3Φ	-	NEMA 1 ENCLOSURE
VFD 2	ABB ACH-550	CHWP-2	10	97	104	32	MECH. RM	460V/3Φ	-	NEMA 1 ENCLOSURE
VFD 3	ABB ACH-550	HWP-1	5	97	104	32	MECH. RM	460V/3Φ	-	NEMA 1 ENCLOSURE
VFD 4	ABB ACH-550	HWP-2	5	97	104	32	MECH. RM	460V/3Φ	-	NEMA 1 ENCLOSURE
VFD 5	ABB ACH-550	RAP-1	1.5	97	104	32	ROOF	460V/3Φ	-	NEMA 3R ENCLOSURE
VFD 6	ABB ACH-550	RAP-2	1.5	97	104	32	ROOF	460V/3Φ	-	NEMA 3R ENCLOSURE

EXHAUST FAN SCHEDULE

NO.	MANUFACTURER & MODEL NO.	TYPE	SERVICE	CFM	ESP	RPM	SONES	BHP	HP	VOLTAGE	OPER. WT. LBS.	REMARKS
EF 1	GREENHECK BCF-212-15	INLINE	1ST FLOOR BATH/SHOWER	430	0.375	869	14.4	1.68	1½	460V/3Φ	515	ELECTRICAL DISCONNECT, PREMIUM EFF. MOTOR, INSULATED CABINET, SIDE ACCESS PANEL.
EF 2	GREENHECK BCF-106--4	INLINE	1ST FLOOR ADAPTED PE SHOWER	350	0.75	1748	7.7	0.08	¼	120 v	80	ELECTRICAL DISCONNECT, PREMIUM EFF. MOTOR, INSULATED CABINET, SIDE ACCESS PANEL.
EF 3	GREENHECK BCF-210-7	INLINE	TRANSFORMER ROOM	3000	0.375	890	12.7	0.63	¾	460V/3Φ	345	ELECTRICAL DISCONNECT, PREMIUM EFF. MOTOR, INSULATED CABINET, SIDE ACCESS PANEL.
EF 4	GREENHECK BCF-212-3	INLINE	2ND FLOOR TOILETS	2280	0.375	604	7.7	0.87	1	460V/3Φ	515	ELECTRICAL DISCONNECT, PREMIUM EFF. MOTOR, INSULATED CABINET, SIDE ACCESS PANEL.
EF 5	GREENHECK BCF-212-3	INLINE	3RD FLOOR TOILETS	2280	0.375	604	7.7	0.87	1	460V/3Φ	515	ELECTRICAL DISCONNECT, PREMIUM EFF. MOTOR, INSULATED CABINET, SIDE ACCESS PANEL.
EF 6	GREENHECK GB-081-6	DOME	3RD FLOOR STERILIZER RM	400	0.5	1244	6.4	0.07	1/6	120 v	-	ELECTRICAL DISCONNECT, ROOF CURB, BIRD SCREEN AND BACKDRAFT DAMPER
EF 7	GREENHECK BCF-108-5	INLINE	2ND FLOOR	1325	0.5	1085	8.0	0.35	½	120V	120	ELECTRICAL DISCONNECT, PREMIUM EFF. MOTOR, INSULATED CABINET, SIDE ACCESS PANEL.

McCARTHY LPA KH

McCarthy Building Companies, Inc.
343 Sansome Street, 14th Floor
San Francisco, California 94104
P 415 |364-1339
F 415 |397-5999

IDENTIFICATION STAMP
DIVISION OF THE STATE ARCHITECT
APPL. 01-
ACC____ FLS____ SS____
DATE_____

REGISTERED PROFESSIONAL ENGINEER
LAURENS VANDEVELDE
NO. 37806
EXP. DATE: 06/30/09
MECHANICAL
STATE OF CALIFORNIA

WESTERN ALLIED MECHANICAL INC
MECHANICAL CONTRACTORS
1580 O'BRIEN DRIVE
MENLO PARK, CA 94025
(650) 324-0750
(650) 321-4546 FAX
STATE CONTRACTOR LICENSE NO. 826782

This design is the exclusive property of Western Allied Mechanical, Inc. The drawings and blueprints containing this design are and shall remain the property of Western Allied Mechanical, Inc. The delivery of the original prints or copies thereof does not constitute a publication thereof.

These drawings or blueprints are exhibited to you solely for the purpose of transacting a sale by Western Allied Mechanical, Inc. of the mechanical system incorporated in the design. Any communication of this design without the written consent of Western Allied Mechanical, Inc. constitutes a violation of the laws of this State.

College of San Mateo
Building 5N
DSA Submittal
San Mateo, CA
Developed for College of San Mateo

Revision	Description	Date

Revision	Description	Date

Job. No.	118051
Date	June 13 2008
Drawn by	RJ
Checked by	LV
Scale	SEE DRAWING

SCHEDULES

M0-02