## **DIVISION 1 GENERAL REQUIREMENTS**

#### **SECTION 01540**

#### SITE SECURITY AND SAFETY

### PART 1 GENERAL

#### 1.1 SUBMITTALS

- A. See Section 01330 (Submittal Procedures).
- B. Site Security
- C. Safety Program.
- D. Fire Protection Plan

### 1.2 PROTECTION

- A. Continuously maintain protection as necessary to protect the Work, as a whole and in part, and adjacent property and improvements from accidents, injuries or damage.
- B. Properly protect the Work:
  - 1. With lights, guard rails, temporary covers and barricades.
  - 2. Enclose excavations with proper barricades.
  - 3. Brace and secure all parts of the Work against storm and accident.
  - 4. Provide such additional forms of protection that may be necessary under existing circumstances.
- C. Provide and maintain in good condition all protective measures required to adequately protect the public from hazards resulting from the Work and to exclude unauthorized persons from the Work. When regulated by Building Code, Cal OSHA, or other authority, such legal requirements for protection shall be considered as minimum requirements. Be responsible for the protection in excess of such minimum requirements as required.

### 1.3 CONTROL OF SITES

Ensure that no alcohol, firearms, weapons, or controlled substance enters or is used at the Sites. Immediately remove from the Sites and terminate the employment of any employee found in violation of this provision.

#### 1.4 SITE SECURITY

- A. As part of the Work included within the Contract Price, Contractor shall take and be fully responsible for all reasonably required measures to protect and maintain the security of persons, existing facilities and property at the Sites, including without limitation preventing theft, loss, vandalism and improper concealment of personal property of the District and all persons lawfully present on the Sites, and including times where workers are not present on the Sites. Contractor's measures shall include, at a minimum, maintaining a log of all persons entering and leaving the Sites and who they represent, what they are delivering and to whom.
- B. No claim shall be made against District by reason of any act of an employee or trespasser, and Contractor shall repair all damage to District's property resulting from Contractor's failure to provide adequate security measures.
- C. Contractor shall maintain a lock on the Construction access gate at all times. Contractor shall appoint one person to let people through the gate and maintain the sign-in/out list, with person's name, company, reason for entering, what they are delivering, time and date. Alternatively, Contractor shall provide a full-time guard at the gate at all times to control access and maintain the sign-in/out list. The sign in/out list shall be available to District at anytime upon request. If District determines that the gate has been left unlocked, Contractor shall if requested by District provide a full time guard at no additional expense to the District.
- D. Contractor shall supply additional security fencing, barricades, lighting, and other security measures as required to protect and control the Sites.

### 1.5 SAFETY PROGRAM

A. Within 15 days after Notice to Proceed, submit a Safety Program that has been reviewed and approved by an Industrial Hygienist certified by the American Board of Industrial Hygiene or a Certified Safety Professional. The Safety Program shall include the name, certification number, and certification seal of the Industrial

- Hygienist or Certified Safety Professional. Comply with the Safety Program and all applicable federal, state, and local regulation codes, rules, law and ordinances.
- B. Receipt and/or review of the Safety Program by District, Engineer or District's representative shall not relieve Contractor of any responsibility for complying with all applicable safety regulations.
- C. It is essential that Contractor and each Subcontractor implement an effective and vigorous Safety and Health Program to cover their respective portions of the Work. Subject to Contractor's overall responsibility for Project safety, it shall be understood that the full responsibility for providing a safe place to work with respect to their respective portions of the Work rests with each individual Contractor and Subcontractor.
- D. Safety Program components:
  - 1. Injury and Illness Prevention Program (IIPP): Conforming to the General Industrial Safety Orders (CCR Title 8, Division 1, Chapter 4, Subchapter 7, Section 3203), and the California Labor Code (Section 6401.7).
  - 2. Site-Specific Safety and Health Plan (SSHP): Describing health and safety procedures that shall be implemented during the Work in order to ensure safety of the public and those performing the Work. Follow the guidelines for a SSHP listed in CCR Title 8, Division 1, Chapter 4, Subchapter 7, Section 5192, Item (b)(4) f.
  - 3. Confined Space Program: The Sites contain permit- and non-permit-confined spaces. District will provide Contractor with any available information regarding permit space hazards, entry operations, and safety information relating to work in the permit spaces as set forth in the General Industrial Safety Orders (CCR Title 8, Division 1, Chapter 4, Subchapter 7, Section 5157). Permit space entry is allowed only through compliance with a permit space program meeting the requirements of Section 5157 of the General Industrial Safety Orders. During entry operations, or at the conclusion of entry operations, verbally notify Engineer of the permit space program followed and of any hazards confronted or created in permit spaces during entry operations.
- E. The wearing of hard hats shall be mandatory at all times for personnel on Site. Supply sufficient hard hats to equip properly all employees and visitors.
- F. Whenever an exposure exists, appropriate personal protective equipment (PPE) shall be used by all affected personnel. Supply PPE to all personnel under Contractor's direction.

# 1.6 SAFETY REQUIREMENTS

- A. Standards: Maintain the Project in accordance with state and local safety and insurance standards.
- B. Hazards Control:
  - 1. Store volatile wastes in covered metal containers and remove from premises daily.
  - 2. Prevent accumulation of wastes that create hazardous conditions.
  - 3. Provide adequate ventilation during use of volatile or noxious substances.
- C. Conduct cleaning and disposal operations to comply with local ordinances and anti-pollution laws.
  - 1. Do not burn or bury rubbish or waste material on the Sites.
  - 2. Do not dispose of volatile wastes such as mineral spirits, oil, or paint thinner in storm or sanitary drains.
  - 3. Do not dispose of wastes into streams or waterways.
- D. Provide accident information on the forms provided by Contractor. This information shall be provided on the same day as the occurrence of said incident.

### 1.7 SITE SAFETY OFFICER

- A. Designate one of Contractor's staff as "Site Safety Officer" whose duties shall include the responsibility for enforcing the environmental protection provisions of the Contract Documents including safety and health, the requirements of the Occupational Safety and Health Act, and other applicable federal, state and local standards. Submit for review by District Contractor's intended traffic flow plan, security plan, program for temporary structures, housecleaning plan, demolition program, and environmental safety and health plan. After review by District, the implementation and enforcement of these plans shall become the responsibility of the Site Safety Officer. Any changes in the plans shall be requested by Contractor through the Site Safety Officer for written concurrence by District.
- B. District's risk management representative(s) shall be allowed access to accident/injury and illness reports, inspection reports, scheduling and construction meetings, and safety meetings.

#### **END OF SECTION**