Page 1 of 2 Chapter 10 - Means of Egrss STATE INFORMATION o [2007 California Building Code, Title 24, Part 2 (First Printing), includes Supplements through Jan 09] Chapter 10 - Means of Egrss SECTION 1001 ADMINISTRATION SECTION 1002 DEFINITIONS SECTION 1003 GENERAL MEANS OF EGRESS SECTION 1004 OCCUPANT LOAD SECTION 1005 EGRESS WIDTH SECTION 1006 MEANS OF EGRESS ILLUMINATION SECTION 1007 ACCESSIBLE MEANS OF EGRESS SECTION 1008 DOORS, GATES AND TURNSTILES SECTION 1009 STAIRWAYS SECTION 1010 RAMPS SECTION 1011 EXIT SIGNS SECTION 1012 HANDRAILS SECTION 1013 GUARDS SECTION 1014 EXIT ACCESS SECTION 1015 EXIT AND EXIT ACCESS DOORWAYS SECTION 1016 EXIT ACCESS TRAVEL DISTANCE SECTION 1017 CORRIDORS SECTION 1018 EXITS ■ SECTION 1019 NUMBER OF EXITS AND CONTINUITY ■ SECTION 1020 VERTICAL EXIT ENCLOSURES SECTION 1021 EXIT PASSAGEWAYS SECTION 1022 HORIZONTAL EXITS ■ SECTION 1023 EXTERIOR EXIT RAMPS AND STAIRWAYS SECTION 1024 EXIT DISCHARGE SECTION 1025 ASSEMBLY SECTION 1026 EMERGENCY ESCAPE AND RESCUE 1017.1 Construction. 1017.2 Corridor width. 1017.3 Dead ends. 1017.4 Air movement in corridors. 1017.5 Corridor continuity. Top Previous Section Next Section SECTION 1017 CORRIDORS 1017.1 Construction. Corridors shall be fire-resistance rated in accordance with Table 1017.1. The corridor walls required to be fireresistance rated shall comply with Section 708 for fire partitions. Exceptions: 1. A fire-resistance rating is not required for corridors in an occupancy in Group E where each room that is used for instruction has at least one door directly to the exterior and rooms for assembly purposes have at least onehalf of the required means of egress doors opening directly to the exterior. Exterior doors specified in this exception are required to be at ground level. Page 2 of 2 Chapter 10 - Means of Egrss 2. A fire-resistance rating is not required for corridors contained within a dwelling or sleeping unit in an occupancy in Group R. 3. A fire-resistance rating is not required for corridors in open parking garages. 4. A fire-resistance rating is not required for corridors in an occupancy in Group B which is a space requiring only a single means of egress complying with Section 1015.1. Top Previous Section Next Section COPYRIGHT 2007 by INTERNATIONAL CODE COUNCIL, powered by citation® Page 2 of 2 Chapter 10 - Means of Egrss 4. Seventy-two inches (1829 mm)—In Group E with a corridor having a required capacity of 100 or more. 5. Seventy-two inches (1829 mm)—In corridors serving surgical Group I, health care centers for ambulatory patients receiving outpatient medical care, which causes the patient to be not capable of self-preservation. 6. Ninety-six inches (2438 mm)—In Group I-2 and I-3 occupancies in areas where required for bed movement or corridors in Group I-2 and I-3 occupancies serving any area caring for one or more nonambulatory persons. TABLE 1017.1 CORRIDOR FIRE-RESISTANCE RATING REQUIRED FIRE-RESISTANCE RATING OCCUPANT LOAD SERVED BY Without sprinkler With sprinkler system^e CORRIDOR OCCUPANCY Not Permitted H-1, H-2, H-3 Not Permitted Greater than 30 H-4, H-5, LGreater than 30 A^d , B, F, M, S, U Not Permitted Greater than 10 Not Permitted Greater than 6 I-2^a, *I-2.1*, I-4 Not Permitted

Top Previous Section Next Section COPYRIGHT 2007 by INTERNATIONAL CODE COUNCIL, powered by citation®

Greater than 6 Greater than 10

http://publicecodes.citation.com/st/ca/st/b200v07/st_ca_st_b200v07_10_sec017_par001.htm?bu=CA-P-20... 8/6/2010