



SHEET KEYNOTES

- ① REMOVE (E) WALL MOUNTED WATER CLOSET INCLUDING CARRIER, FLUSHMETER VALVE, TOILET SEAT AND RELATED PIPING. CAP (E) WASTE PIPE BELOW THE FLOOR AND CAP VENT PIPE ABOVE THE FLOOR INSIDE THE WALL.
- ② REMOVE (E) URINAL INCLUDING STOP VALVES AND RELATED PIPING. CAP (E) WASTE PIPE BELOW THE FLOOR AND CAP VENT PIPE ABOVE THE FLOOR INSIDE THE WALL.
- ③ REMOVE (E) WALL MOUNTED LAVATORY INCLUDING DRAIN, P-TRAP, SUPPLY TUBING, STOP VALVES AND RELATED PIPING. CAP (E) WASTE PIPE BELOW THE FLOOR AND CAP VENT PIPE ABOVE THE FLOOR INSIDE THE WALL. PATCH HOLE TO MATCH (E) WALL.
- ④ (E) FD AND RELATED PIPING TO BE REMOVED, PATCH FLOOR SLAB TO MATCH (E) FLOOR SLAB.
- ⑤ (E) PIPING TO REMAIN.
- ⑥ REMOVE (E) HOSE BIBB AND RELATED PIPING.
- ⑦ (E) PIPE RISER TO REMAIN.
- ⑧ PROVIDE CAP ON (E) PIPING.
- ⑨ REMOVE (E) SINK AND ASSOCIATED APPURTENANCES, CAP PIPING AND CONCEALED TO WALL. PATCH HOLE TO MATCH (E) FINISHED FLOOR/WALL.
- ⑩ REMOVE (E) JANITOR SINK INCLUDING STOP VALVES AND RELATED PIPING. CAP (E) WASTE PIPE BELOW THE FLOOR AND CAP VENT PIPE ABOVE THE FLOOR INSIDE THE WALL.

R.L. →
NOT DONE

REF-72.1
Storm Drain Change

1 FIRST FLOOR DEMOLITION PLAN - PLUMBING
 0 4' 8' 16'
 SCALE: 1/8"=1'-0"

PROJECT 2007-0731
CONTACT Omar Hawit

INTERFACE
ENGINEERING

717 Market Street
Suite 500
San Francisco, CA 94103
TEL 415.489.7240
FAX 415.489.7289
www.interfaceengineering.com

ARCHITECT ENGINEER

LICENSED ARCHITECT
PAUL CURTIS BUNTON
No. 00186596
Exp. 12/31/2009
STATE OF CALIFORNIA

REGISTERED PROFESSIONAL ENGINEER
MECHANICAL
No. 030802
Exp. 12-31-2009
STATE OF CALIFORNIA

- GENERAL NOTES
1. This sheet is part of a set and is not to be used alone.
 2. This sheet is not to be used for construction unless the architect's stamp and signature appear on the drawings and the status box indicates drawings have been released for construction.
 3. These plans and prints thereof, as instruments of service, are owned by the architect and are for use on this project only. Reproduction and/or distribution without the prior written consent of the architect is forbidden.
 4. Copyright Bunton Clifford Associates, 2007

REVISION HISTORY	REMARKS	DATE

DRAWING STATUS	DATE

FILE NO. 41-C1

IDENTIFICATION STAMP
DIV. OF THE STATE ARCHITECT

01-110074
DATE MAR 19 2009

**BUILDINGS 5 & 6
RENOVATIONS**

San Mateo County Community
College District

DSA BACK-CHECK

CAÑADA COLLEGE
4200 Farm Hill Boulevard
Redwood City, CA 94061

FIRST FLOOR
DEMOLITION PLAN
PLUMBING