


1 | 2 | 3 | **GRAB BAR BLOCKING DETAIL** | 4

SCALE: 3/8"=1'-0"



5 | **RESTROOM DOOR SIGNAGE DETAIL**

SCALE: 3/8"=1'-0"

6 | 7 | 8 | 9

NAMES, NUMBERS, OR LETTERS ONLY
THE MOST LOGICAL IDENTIFICATION SYSTEM FOR ROOMS OR OFFICES IS TO USE NUMBERS, LETTERS, OR COMBINATIONS OF NUMBERS AND LETTERS WHICH CAN THEN BE ARRANGED IN LOGICAL ORDER FOR EASY WAYFINDING.

12B Braille
LIBRARY Braille
EXIT Braille

RAISED CHARACTERS:
UPPERCASE CHARACTERS ARE RAISED 1/32" FROM SURFACE OF SIGN. TYPESTYLE MUST BE SANS SERIF, WITH A STROKE WIDTH BETWEEN 10 AND 20 PERCENT OF HEIGHT, HEIGHT IS BETWEEN 5/8" AND 2". WIDTH OF CHARACTER IS BETWEEN 60 PERCENT AND 100 PERCENT OF HEIGHT.

FINISH
TEXT AND PICTOGRAMS MUST CONTRAST WITH BACKGROUND OF SIGN A MINIMUM OF 10 PERCENT IS DESIRABLE. SIGN MUST HAVE A NON-GLARE FINISH. CHANGEABLE INFORMATION MAY BE INCLUDED ON A REMOVABLE INSERT

BRAILLE
CALIFORNIA CONTRACTED GRADE 2 BRAILLE IS REQUIRED. CAPITAL LETTER INDICATORS SHOULD BE USED ONLY FOR INDIVIDUAL LETTERS, INITIALS, ACRONYMS, AND PROPER NOUNS. DOTS WITHIN A CELL MUST BE 1/10TH INCH ON CENTER. CELLS MUST BE 2/10 INCH APART, MEASURED FROM THE CENTER OF THE DOTS IN ROW TWO TO THE CENTER OF THE DOTS IN ROW ONE OF THE CELL ON THE RIGHT IN THE SAME WORD. DOTS SHOULD BE ROUNDED OR DOMED AND MUST BE 1/40 INCH HIGH MINIMUM.

LAYOUT
CENTERED LAYOUT IS OPTIONAL. BRAILLE SHOULD BE BELOW RAISED CHARACTERS WITH 1/2 INCH SPACE BETWEEN. NOTE THE TACTILE INFORMATION AND BRAILLE IS BELOW THE CENTER LINE IN THE LARGER SIGNS. THIS MAKES IT EASIER FOR CHILDREN TO REACH.

ACCESSIBLE ENTRANCES
IDENTIFY ACCESSIBLE ENTRANCES WITH THE "INTERNATIONAL SYMBOL OF ACCESSIBILITY".

WHEN ALL ENTRANCES ARE NOT ACCESSIBLE, A SIGN IS INSTALLED AT EACH ACCESSIBLE ENTRANCE. HOWEVER, WHEN INDIVIDUAL CLASSROOMS ARE INVOLVED, WHETHER OFF AN INTERIOR CORRIDOR OR FROM THE EXTERIOR OF THE BUILDING, IT MAY BE POSSIBLE TO AVOID HAVING AN INDIVIDUAL INTERNATIONAL SYMBOL OF ACCESSIBILITY (ISA) AT EACH DOOR BY USING ONE SIGN PER ELEVATION OR BUILDING.

PROPORTIONS:
CHARACTERS ON SIGNS SHALL BE SELECTED FROM FONTS THAT HAVE A WIDTH-TO-HEIGHT RATIO BETWEEN 3/5 (60%) AND 11/100% MEASURED BY THE WIDTH OF THE UPPERCASE LETTER "O" AND HEIGHT OF THE UPPERCASE LETTER "I" AND A STROKE WIDTH-TO-HEIGHT RATIO BETWEEN 1/5 (20%) AND 1/10 (10%) MEASURED BY THE WIDTH AND HEIGHT OF THE UPPERCASE LETTER "I".

VISUAL CHARACTER HEIGHT:
FOR DIRECTIONAL, INFORMATIONAL, AND ACCESSIBILITY (SIGNS THAT IDENTIFY, DIRECT TO OR GIVE INFORMATION ABOUT ACCESSIBLE ELEMENTS AND FEATURES OF A BUILDING OR SITE) SHALL BE SIZED PER C.B.C. TABLE 11B3.4.
VIEWING DISTANCE SHALL BE MEASURED AS THE HORIZONTAL DISTANCE BETWEEN THE CHARACTER AND AN OBSTRUCTION PREVENTING FURTHER APPROACH TOWARD THE SIGN.

NOTE
ROOM IDENTIFICATION SIGNAGE AND INTERNATIONAL SYMBOLS OF ACCESSIBILITY SIGNAGE SHALL BE PROVIDED BY SCHOOL DISTRICT / OWNER AT SITE. SIGNAGE SHALL BE INSTALLED AT LOCATIONS REQUIRED BY CODE USING THE ABOVE GUIDELINES.

10 | **TYP. ROOM IDENTIFICATION SIGNAGE**

DIVISION OF THE STATE ARCHITECT

REV / DATE:

JOB No.: 12-19
DRAWN BY: JM
DATE: 07-18-12

THIS MODULAR S.D.G. HAS BEEN ENGINEERED BY A REGISTERED STRUCTURAL ENGINEER AND PREVIOUSLY REVIEWED & APPROVED BY THE DIVISION OF THE STATE ARCHITECT, FIRE & LIFE SAFETY AND ACCESS COMPLIANCE SECTION

CONFIDENTIAL MATERIAL—THESE DOCUMENTS ARE THE PROPERTY OF AND ARE NOT TO BE REPRODUCED OR DISTRIBUTED WITHOUT FULL KNOWLEDGE AND WRITTEN CONSENT FROM ENVIROPLEX, INC.
© COPYRIGHT ENVIROPLEX, INC. (ALL DRAWINGS PREPARED BY ENVIROPLEX, INC.)

11 | 12 | 13 | 14

10 | **TYP. ROOM IDENTIFICATION SIGNAGE**

DIVISION OF THE STATE ARCHITECT

REV / DATE:

JOB No.: 12-19
DRAWN BY: JM
DATE: 07-18-12

THIS MODULAR S.D.G. HAS BEEN ENGINEERED BY A REGISTERED STRUCTURAL ENGINEER AND PREVIOUSLY REVIEWED & APPROVED BY THE DIVISION OF THE STATE ARCHITECT, FIRE & LIFE SAFETY AND ACCESS COMPLIANCE SECTION

CONFIDENTIAL MATERIAL—THESE DOCUMENTS ARE THE PROPERTY OF AND ARE NOT TO BE REPRODUCED OR DISTRIBUTED WITHOUT FULL KNOWLEDGE AND WRITTEN CONSENT FROM ENVIROPLEX, INC.
© COPYRIGHT ENVIROPLEX, INC. (ALL DRAWINGS PREPARED BY ENVIROPLEX, INC.)

CYS
STRUCTURAL ENGINEERS INC.
1700 Cocksidge Oaks Dr., Suite 108
San Mateo, CA 94403
(415) 920-1550
(415) 920-2020 (FAX) 920-1550 FAX
www.cysinc.com

REGISTERED PROFESSIONAL ENGINEER
ARCHITECT
No. S2030
EXP. 9/30/13
STRUCTURAL
STATE OF CALIFORNIA

THESE DRAWINGS ARE PRELIMINARY AND NOT FOR CONSTRUCTION UNLESS STAMPED & SIGNED BY THE ENGINEER OF RECORD.

ENVIROPLEX, INC.
4777 E. CARPENTER ROAD STOCKTON, CA. 95215, (209) 466-8000
11) 12-19 RELOCATABLE RESTROOM BUILDINGS FOR LA CANADA COLLEGE
SAN MATEO COMMUNITY COLLEGE DISTRICT

MISCELLANEOUS DETAILS

PRELIMINARY