San Mateo County Community College District Actuarial Study of Retiree Health Liabilities Under GASB 74/75 Roll-forward Valuation Valuation Date: June 30, 2017 Measurement Date: June 30, 2018

Prepared by: Total Compensation Systems, Inc.

Date: October 4, 2018

Table of Contents

A. Introduction	3
B. General Findings	
C. DESCRIPTION OF RETIREE BENEFITS	
D. RECOMMENDATIONS.	
PART II: BACKGROUND	
	•••• /
A. SUMMARY 7	
B. ACTUARIAL ACCRUAL	7
PART III: LIABILITIES AND COSTS FOR RETIREE BENEFITS	9
A. Introduction.	9
B. Liability for Retiree Benefits	9
C. Cost to Prefund Retiree Benefits	
1. Service Cost	
2. Total OPEB Liability (TOL) and Net OPEB Liability (NOL)	10
3. OPEB Expense	11
4. Deferred Inflows and Outflows	
PART IV: "PAY AS YOU GO" FUNDING OF RETIREE BENEFITS	
PARTIV: PAT AS TOU GO FUNDING OF RETIREE DENEFTIS	14
PART V: RECOMMENDATIONS FOR FUTURE VALUATIONS	13
PART VI: APPENDICES	14
APPENDIX A: MATERIALS USED FOR THIS STUDY	
APPENDIX B: EFFECT OF ASSUMPTIONS USED IN CALCULATIONS	15
APPENDIX C: ACTUARIAL ASSUMPTIONS AND METHODS	
APPENDIX D: DISTRIBUTION OF ELIGIBLE PARTICIPANTS BY AGE	
APPENDIX E: GASB 74/75 ACCOUNTING ENTRIES AND DISCLOSURES	
APPENDIX F: DEFERRED OUTFLOWS OF RESOURCES AND DEFERRED INFLOWS OF RESOURCES	
APPENDIX G: GLOSSARY OF RETIREE HEALTH VALUATION TERMS	

San Mateo County Community College District Actuarial Study of Retiree Health Liabilities

PART I: EXECUTIVE SUMMARY

A. Introduction

San Mateo County Community College District engaged Total Compensation Systems, Inc. (TCS) to analyze liabilities associated with its current retiree health program as of June 30, 2018 (the measurement date). This valuation report is based on an earlier GASB 75 valuation as of June 30, 2017. We used standard actuarial "roll-forward" methodology to estimate the Total OPEB Liability (TOL) as of the measurement date. The Fiduciary Net Position (FNP) is based on the actual FNP at June 30, 2018. The numbers in this report are based on the assumption that they will first be used to determine accounting entries for the fiscal year ending June 30, 2018. If the report will first be used for a different fiscal year, the numbers may need to be adjusted accordingly.

This report does not reflect any cash benefits paid unless the retiree is required to provide proof that the cash benefits are used to reimburse the retiree's cost of health benefits. Costs and liabilities attributable to cash benefits paid to retirees are reportable under applicable Governmental Accounting Standards Board (GASB) Standards.

This actuarial study is intended to serve the following purposes:

- To provide information to enable San Mateo CCD to manage the costs and liabilities associated with its retiree health benefits.
- To provide information to enable San Mateo CCD to communicate the financial implications of retiree health benefits to internal financial staff, the Board, employee groups and other affected parties.
- To provide information needed to comply with Governmental Accounting Standards Board Accounting Standards 74 and 75 related to "other postemployment benefits" (OPEB's).

Because this report was prepared in compliance with GASB 74 and 75, San Mateo CCD should not use this report for any other purpose without discussion with TCS. This means that any discussions with employee groups, governing Boards, etc. should be restricted to the implications of GASB 74 and 75 compliance.

We calculated the following estimates separately for active employees and retirees. As requested, we also separated results by the following employee classifications: AFSCME, Certificated Management, Faculty, Classified and Classified Management. We estimated the following:

- the total liability created. (The actuarial present value of total projected benefit payments or APVPBP)
- ten years of projected benefit payments.
- the "total OPEB liability (TOL)." (The TOL is the portion of the APVPBP attributable to employees' service prior to the measurement date.)
- the "net OPEB liability" (NOL). For plans funded through a trust, this represents the unfunded portion of the liability.

- the service cost (SC). This is the value of OPEB benefits earned for one year of service.
- deferred inflows and outflows of resources attributable to the OPEB plan.
- "OPEB expense." This is the amount recognized in accrual basis financial statements as the current period expense. The OPEB expense includes service cost, interest and certain changes in the OPEB liability, adjusted to reflect deferred inflows and outflows. This amount may need to be adjusted to reflect any contributions received after the Measurement Date.
- Amounts to support financial statement Note Disclosures and Required Supplementary Information (RSI) schedules.

We summarized the data used to perform this study in Appendix A. No effort was made to verify this information beyond brief tests for reasonableness and consistency.

All cost and liability figures contained in this study are estimates of future results. Future results can vary dramatically and the accuracy of estimates contained in this report depends on the accuracial assumptions used. Service costs and liabilities could easily vary by 10 - 20% or more from estimates contained in this report.

B. General Findings

We estimate the "pay-as-you-go" cost of providing retiree health benefits in the year beginning July 1, 2018 to be \$7,432,730 (see Section IV.A.). The "pay-as-you-go" cost is the cost of benefits for current retirees.

For current employees, the value of benefits "accrued" in the year beginning July 1, 2018 (the service cost) is \$3,359,195. This service cost would increase each year based on covered payroll. Had San Mateo CCD begun accruing retiree health benefits when each current employee and retiree was hired, a substantial liability would have accumulated. We estimate the amount that would have accumulated at June 30, 2018 to be \$121,063,333. This amount is called the "Total OPEB Liability" (TOL). San Mateo CCD has set aside funds to cover retiree health liabilities in a GASB 75 qualifying trust. The Fiduciary Net Position of this trust at June 30, 2018 was \$114,912,841. This leaves a Net OPEB Liability (NOL) of \$6,150,492.

Based on the information we were provided, the OPEB Expense for the fiscal year ending June 30, 2018 is \$4,813,321. As noted in this report, adjustments may be needed – particularly if the reporting date is not the same as the measurement date.

We based all of the above estimates on employees as of March, 2017. Over time, liabilities and cash flow will vary based on the number and demographic characteristics of employees and retirees.

C. Description of Retiree Benefits

Following is a description of the current retiree benefit plan. District practices are based on Government Code sections collectively known as PEMHCA, which vary from collective bargaining agreements.

	-	Certificated	-	<u>-</u>	Classified
	<i>AFSCME</i>	Management	Certificated	Classified	Management
Benefit types provided	Medical, Part B				
Duration of Benefits	Lifetime	Lifetime	Lifetime	Lifetime	Lifetime
Minimum Age Required Service	Retirement from Applicable Retirement System				
Dependent Coverage	Yes	Yes	Yes	Yes	Yes
District Contribution %	100%	100%	100%	100%	100%
District Cap	\$704 per month*				

^{*}The District contribution is changed periodically. Grandfathered employees and retirees receive benefits that may exceed this cap.

D. Recommendations

It is outside the scope of this report to make specific recommendations of actions San Mateo CCD should take to manage the liability created by the current retiree health program. Total Compensation Systems, Inc. can assist in identifying and evaluating options once this report has been studied. The following recommendations are intended only to allow the District to get more information from this and future studies. Because we have not conducted a comprehensive administrative audit of San Mateo CCD's practices, it is possible that San Mateo CCD is already complying with some or all of our recommendations.

- We recommend that San Mateo CCD maintain an inventory of all benefits and services provided to retirees whether contractually or not and whether retiree-paid or not. For each, San Mateo CCD should determine whether the benefit is material and subject to GASB 74 and/or 75.
- We recommend that San Mateo CCD conduct a study whenever events or contemplated actions significantly affect present or future liabilities, but no <u>less</u> frequently than every two years, as required under GASB 74/75.
- Under GASB 75, it is important to isolate the cost of retiree health benefits. San Mateo CCD should have all premiums, claims and expenses for retirees separated from active employee premiums, claims, expenses, etc. To the extent any retiree benefits are made available to retirees over the age of 65 *even on a retiree-pay-all basis* all premiums, claims and expenses for post-65 retiree coverage should be segregated from those for pre-65 coverage. Furthermore, San Mateo CCD should arrange for the rates or prices of all retiree benefits to be set on what is expected to be a self-sustaining basis.
- San Mateo CCD should establish a way of designating employees as eligible or ineligible for future OPEB benefits. Ineligible employees can include those in ineligible job classes; those hired after a

- designated date restricting eligibility; those who, due to their age at hire cannot qualify for District-paid OPEB benefits; employees who exceed the termination age for OPEB benefits, etc.
- Several assumptions were made in estimating costs and liabilities under San Mateo CCD's retiree health program. Further studies may be desired to validate any assumptions where there is any doubt that the assumption is appropriate. (See Appendices B and C for a list of assumptions and concerns.) For example, San Mateo CCD should maintain a retiree database that includes in addition to date of birth, gender and employee classification retirement date and (if applicable) dependent date of birth, relationship and gender. It will also be helpful for San Mateo CCD to maintain employment termination information namely, the number of OPEB-eligible employees in each employee class that terminate employment each year for reasons other than death, disability or retirement.

Respectfully submitted,

Geoffrey L. Kischuk, FSA, MAAA, FCA

Consultant

Total Compensation Systems, Inc.

(805) 496-1700

PART II: BACKGROUND

A. Summary

Accounting principles provide that the cost of retiree benefits should be "accrued" over employees' working lifetime. For this reason, the Governmental Accounting Standards Board (GASB) issued in June of 2015 Accounting Standards 74 and 75 for retiree health benefits. These standards apply to all public employers that pay any part of the cost of retiree health benefits for current or future retirees (including early retirees), whether they pay directly or indirectly (via an "implicit rate subsidy"),

B. Actuarial Accrual

To actuarially accrue retiree health benefits requires determining the amount to expense each year so that the liability accumulated at retirement is, on average, sufficient (with interest) to cover all retiree health expenditures without the need for additional expenses. There are many different ways to determine the annual accrual amount. The calculation method used is called an "actuarial cost method."

The actuarial cost method mandated by GASB 75 is the "entry age actuarial cost method". Under this method, there are two components of actuarial cost – a "service cost" (SC) and the "Total OPEB Liability" (TOL). GASB 75 allows certain changes in the TOL to be deferred (i.e. deferred inflows and outflows of resources).

The service cost can be thought of as the value of the benefit earned each year if benefits are accrued during the working lifetime of employees. Under the entry age actuarial cost method, the actuary determines the annual amount needing to be expensed from hire until retirement to fully accrue the cost of retiree health benefits. This amount is the service cost. Under GASB 75, the service cost is calculated to be a level percentage of each employee's projected pay.

The service cost is determined using several key assumptions:

- The current *cost of retiree health benefits* (often varying by age, Medicare status and/or dependent coverage). The higher the current cost of retiree benefits, the higher the service cost.
- The "trend" rate at which retiree health benefits are expected to increase over time. A higher trend rate increases the service cost. A "cap" on District contributions can reduce trend to zero once the cap is reached thereby dramatically reducing service costs.
- Mortality rates varying by age and sex. (Unisex mortality rates are not often used as individual OPEB benefits do not depend on the mortality table used.) If employees die prior to retirement, past contributions are available to fund benefits for employees who live to retirement. After retirement, death results in benefit termination or reduction. Although higher mortality rates reduce service costs, the mortality assumption is not likely to vary from employer to employer.
- **Employment termination rates** have the same effect as mortality inasmuch as higher termination rates reduce service costs. Employment termination can vary considerably between public agencies.
- The *service requirement* reflects years of service required to earn full or partial retiree benefits. While a longer service requirement reduces costs, cost reductions are not usually substantial unless the service period exceeds 20 years of service.

- Retirement rates determine what proportion of employees retire at each age (assuming employees reach the requisite length of service). Retirement rates often vary by employee classification and implicitly reflect the minimum retirement age required for eligibility. Retirement rates also depend on the amount of pension benefits available. Higher retirement rates increase service costs but, except for differences in minimum retirement age, retirement rates tend to be consistent between public agencies for each employee type.
- **Participation rates** indicate what proportion of retirees are expected to elect retiree health benefits if a significant retiree contribution is required. Higher participation rates increase costs.
- The *discount rate* estimates investment earnings for assets earmarked to cover retiree health benefit liabilities. The discount rate depends on the nature of underlying assets for funded plans. The rate used for a funded plan is the real rate of return expected for plan assets plans plus long term inflation assumption. For an unfunded plan, the discount rate is based on an index of 20 year General Obligation municipal bonds. For partially funded plans, the discount rate is a blend of the funded and unfunded rates.

The assumptions listed above are not exhaustive, but are the most common assumptions used in actuarial cost calculations. If all actuarial assumptions are exactly met and an employer expensed the service cost every year for all past and current employees and retirees, a sizeable liability would have accumulated (after adding interest and subtracting retiree benefit costs). The liability that would have accumulated is called the Total OPEB Liability (TOL). The excess of TOL over the value of plan assets is called the Net OPEB Liability (NOL). Under GASB 74 and 75, in order for assets to count toward offsetting the TOL, the assets have to be held in an irrevocable trust that is safe from creditors and can only be used to provide OPEB benefits to eligible participants.

The total OPEB liability (TOL) can arise in several ways - e.g., as a result of plan changes or changes in actuarial assumptions. TOL can also arise from actuarial gains and losses. Actuarial gains and losses result from differences between actuarial assumptions and actual plan experience.

Under GASB 74 and 75, a portion of actuarial gains and losses can be deferred as follows:

- ➤ Investment gains and losses can be deferred five years
- Experience gains and losses can be deferred over the expected average remaining service lives (EARSL) of plan participants. In calculating the EARSL, terminated employees (primarily retirees) are considered to have a working lifetime of zero. This often makes the EARSL quite short.
- Liability changes resulting from changes in economic and demographic assumptions are also deferred based on the average working lifetime
- Liability changes resulting from plan changes, for example, cannot be deferred.

PART III: LIABILITIES AND COSTS FOR RETIREE BENEFITS

A. Introduction.

The liability for OPEB benefits was calculated in the valuation as of June 30, 2017 and the methodology used was described in our GASB 75 valuation report dated September 26, 2017. In Part III, we show the tables included in our September 26, 2017 valuation report and provide details of our roll-forward valuation.

We summarized actuarial assumptions used for this study in Appendix C.

B. Liability for Retiree Benefits.

Below is the actuarial present value of projected benefit payments (APVPBP) table presented in our September 26, 2017 valuation report.

Actuarial Present Value of Projected Benefit Payments at June 30, 2017

	-		Certificated			Classified
	Total	AFSCME	Management	Faculty	Classified	Management
Active: Pre-65	\$16,808,530	\$1,567,787	\$750,650	\$6,365,017	\$5,416,091	\$2,708,985
Post-65	\$51,890,784	\$4,483,082	\$3,085,602	\$20,233,337	\$16,157,941	\$7,930,822
Subtotal	\$68,699,314	\$6,050,869	\$3,836,252	\$26,598,354	\$21,574,032	\$10,639,807
Retiree: Pre-65	\$2,620,675	\$952,894	\$32,252	\$332,024	\$903,583	\$399,922
Post-65	\$67,772,835	\$1,444,095	\$683,596	\$33,336,922	\$28,750,701	\$3,557,521
Subtotal	\$70,393,510	\$2,396,989	\$715,848	\$33,668,946	\$29,654,284	\$3,957,443
Grand Total	\$139,092,824	\$8,447,858	\$4,552,100	\$60,267,300	\$51,228,316	\$14,597,250
Subtotal Pre-65	\$19,429,205	\$2,520,681	\$782,902	\$6,697,041	\$6,319,674	\$3,108,907
Subtotal Post-65	\$119,663,619	\$5,927,177	\$3,769,198	\$53,570,259	\$44,908,642	\$11,488,343

C. Cost to Prefund Retiree Benefits

1. Service Cost

Below is the service cost table included in our September 26, 2017 valuation report. This service cost is used in calculating the pension expense.

Service Cost Year Beginning June 30, 2017

			Certificated			Classified
	Total	AFSCME	Management	Faculty	Classified	Management
# of Employees	947	87	54	322	339	145
Per Capita Service Cost						
Pre-65 Benefit	N/A	\$1,142	\$1,170	\$1,268	\$1,012	\$1,078
Post-65 Benefit	N/A	\$2,218	\$3,398	\$2,856	\$2,008	\$2,153
First Year Service Cost						
Pre-65 Benefit	\$1,070,208	\$99,354	\$63,180	\$408,296	\$343,068	\$156,310
Post-65 Benefit	\$2,288,987	\$192,966	\$183,492	\$919,632	\$680,712	\$312,185
Total	\$3,359,195	\$292,320	\$246,672	\$1,327,928	\$1,023,780	\$468,495

2. Total OPEB Liability (TOL) and Net OPEB Liability (NOL)

The table below shows the TOL included in the September 26, 2017 valuation report. This TOL is used as the beginning of year TOL to roll forward the TOL to June 30, 2018.

Total OPEB Liability (TOL) and Net OPEB Liability (NOL) as of June 30, 2017

			Certificated			Classified
	Total	AFSCME	Management	Faculty	Classified	Management
Active: Pre-65	\$9,733,470	\$912,634	\$403,159	\$3,739,408	\$3,017,800	\$1,660,469
Active: Post-65	\$36,842,525	\$3,210,640	\$2,076,394	\$14,319,506	\$11,399,276	\$5,836,709
Subtotal	\$46,575,995	\$4,123,274	\$2,479,553	\$18,058,914	\$14,417,076	\$7,497,178
Retiree: Pre-65	\$2,620,675	\$952,894	\$32,252	\$332,024	\$903,583	\$399,922
Retiree: Post-65	\$67,772,835	\$1,444,095	\$683,596	\$33,336,922	\$28,750,701	\$3,557,521
Subtotal	\$70,393,510	\$2,396,989	\$715,848	\$33,668,946	\$29,654,284	\$3,957,443
Subtotal: Pre-65	\$12,354,145	\$1,865,528	\$435,411	\$4,071,432	\$3,921,383	\$2,060,391
Subtotal: Post-65	\$104,615,360	\$4,654,735	\$2,759,990	\$47,656,428	\$40,149,977	\$9,394,230
Total OPEB Liability (TOL)	\$116,969,506	\$6,520,264	\$3,195,401	\$51,727,860	\$44,071,360	\$11,454,621
Fiduciary Net Position as of	_					
June 30, 2017	\$97,061,619					
Net OPEB Liability (NOL)	\$19,907,887					

In order to determine the June 30, 2018 NOL, we used a "roll-forward" technique for the TOL. The FNP is based on the actual June 30, 2018 FNP. The following table shows the results of the roll-forward.

Changes in Net OPEB Liability as of June 30, 2018

	TOL	FNP	NOL
Balance at June 30, 2017	\$116,969,506	\$97,061,619	\$19,907,887
Service Cost	\$3,359,195	\$0	\$3,359,195
Interest on TOL	\$8,049,420	\$0	\$8,049,420
Employer Contributions	\$0	\$19,514,788	(\$19,514,788)
Employee Contributions	\$0	\$0	\$0
Assumption Changes	\$0	\$0	\$0
Expected Investment Income	\$0	\$7,208,125	(\$7,208,125)
Investment Gains/Losses	\$0	(\$1,180,091)	\$1,180,091
Administrative Expense	\$0	(\$376,812)	\$376,812
Expected Benefit Payments	(\$7,314,788)	(\$7,314,788)	\$0
Actual minus Expected Benefit Payments	\$0	\$0	\$0
Other	\$0	\$0	\$0
Net Change during 2017-18	\$4,093,827	\$17,851,222	(\$13,757,395)
Balance at June 30, 2018 *	\$121,063,333	\$114,912,841	\$6,150,492

^{*} May include a slight rounding error.

3. OPEB Expense

Under GASB 74 and 75, OPEB expense includes service cost, interest cost, change in TOL due to plan changes; all adjusted for deferred inflows and outflows. Following is the pension expense for the fiscal year ending June 30, 2018. The OPEB expense shown below is considered to be preliminary because there can be employer specific deferred items (e.g., contributions made after the measurement date, and active employee contributions toward the OPEB plan).

OPEB Expense Fiscal Year Ending June 30, 2018

	Total
Service Cost	\$3,359,195
Interest on Total OPEB Liability (TOL)	\$8,049,420
Employee Contributions	\$0
Recognized Experience Gains/Losses	\$0
Recognized Assumption Changes	\$0
Expected Investment Income	(\$7,208,125)
Recognized Investment Gains/Losses	\$236,019
Contributions After Measurement Date*	\$0
Liability Change Due to Benefit Changes	\$0
Administrative Expense	\$376,812
OPEB Expense**	\$4,813,321

^{*} Should be added by San Mateo CCD if reporting date is after the measurement date.

The above OPEB expense does not include an estimated \$19,514,788 in employer contributions.

4. Deferred Inflows and Outflows

Certain types of TOL changes are subject to deferral, as are investment gains/losses. Appendix F provides details of any deferred inflows and/or outflows included in the pension expense.

^{**} May include a slight rounding error.

PART IV: "PAY AS YOU GO" FUNDING OF RETIREE BENEFITS

We used the actuarial assumptions shown in Appendix C to project the District's ten year retiree benefit outlay, including any implicit rate subsidy. Because these cost estimates reflect average assumptions applied to a relatively small number of employees, estimates for individual years are **certain** to be **in**accurate. However, these estimates show the size of cash outflow.

The following table shows a projection of annual amounts needed to pay the District's share of retiree health costs, including any implicit rate subsidy, that was included in the September 26, 2017 valuation report.

Year Beginning			Certificated			Classified
July 1	Total	AFSCME	Management	Faculty	Classified	Management
2017	\$7,314,788	\$191,647	\$70,469	\$3,548,404	\$3,128,744	\$375,524
2018	\$7,432,730	\$218,226	\$87,241	\$3,607,605	\$3,117,697	\$401,961
2019	\$7,760,083	\$268,491	\$110,577	\$3,751,754	\$3,166,081	\$463,180
2020	\$8,064,880	\$314,259	\$135,172	\$3,867,195	\$3,222,086	\$526,168
2021	\$8,341,011	\$359,540	\$156,935	\$3,955,606	\$3,278,088	\$590,842
2022	\$8,563,287	\$387,822	\$180,464	\$4,019,277	\$3,327,941	\$647,783
2023	\$8,816,012	\$416,144	\$206,627	\$4,103,325	\$3,379,229	\$710,687
2024	\$9,034,350	\$435,607	\$231,946	\$4,165,609	\$3,423,891	\$777,297
2025	\$9,237,976	\$467,438	\$262,203	\$4,210,173	\$3,460,958	\$837,204
2026	\$9,446,255	\$501,158	\$295,362	\$4,254,545	\$3,499,199	\$895,991

PART V: RECOMMENDATIONS FOR FUTURE VALUATIONS

To effectively manage benefit costs, an employer must periodically examine the existing liability for retiree benefits as well as future annual expected premium costs. GASB 74/75 require biennial valuations. In addition, a valuation should be conducted whenever plan changes, changes in actuarial assumptions or other employer actions are likely to cause a material change in accrual costs and/or liabilities.

Following are examples of actions that could trigger a new valuation.

- An employer should perform a valuation whenever the employer considers or puts in place an early retirement incentive program.
- An employer should perform a valuation whenever the employer adopts a retiree benefit plan for some or all employees.
- An employer should perform a valuation whenever the employer considers or implements changes to retiree benefit provisions or eligibility requirements.
- An employer should perform a valuation whenever the employer introduces or changes retiree contributions.
- An employer should perform a valuation whenever the employer forms a qualifying trust or changes its investment policy.
- An employer should perform a valuation whenever the employer adds or terminates a group of participants that constitutes a significant part of the covered group.

We recommend San Mateo CCD take the following actions to ease future valuations.

We have used our training, experience and information available to us to establish the actuarial assumptions used in this valuation. We have no information to indicate that any of the assumptions do not reasonably reflect future plan experience. However, the District should review the actuarial assumptions in Appendix C carefully. If the District has any reason to believe that any of these assumptions do not reasonably represent the expected future experience of the retiree health plan, the District should engage in discussions or perform analyses to determine the best estimate of the assumption in question.

PART VI: APPENDICES

APPENDIX A: MATERIALS USED FOR THIS STUDY

We relied on the following materials to complete this study.

- We used paper reports and digital files containing employee demographic data from the District personnel records.
- We used relevant sections of collective bargaining agreements provided by the District.

APPENDIX B: EFFECT OF ASSUMPTIONS USED IN CALCULATIONS

While we believe the estimates in this study are reasonable overall, it was necessary for us to use assumptions which inevitably introduce errors. We believe that the errors caused by our assumptions will not materially affect study results. If the District wants more refined estimates for decision-making, we recommend additional investigation.

APPENDIX C: ACTUARIAL ASSUMPTIONS AND METHODS

Following is a summary of actuarial assumptions and methods used in this study. The District should carefully review these assumptions and methods to make sure they reflect the District's assessment of its underlying experience. It is important for San Mateo CCD to understand that the appropriateness of all selected actuarial assumptions and methods are San Mateo CCD's responsibility. Unless otherwise disclosed in this report, TCS believes that all methods and assumptions are within a reasonable range based on the provisions of GASB 74 and 75, applicable actuarial standards of practice, San Mateo CCD's actual historical experience, and TCS's judgment based on experience and training.

ACTUARIAL METHODS AND ASSUMPTIONS:

<u>ACTUARIAL COST METHOD:</u> GASB 74/75 require use of the entry age actuarial cost method.

Entry age is based on the age at hire for eligible employees. The attribution period is determined as the difference between the expected retirement age and the age at hire. The APVPBP and present value of future service costs are determined on an employee by employee basis and then aggregated.

To the extent that different benefit formulas apply to different employees of the same class, the service cost is based on the benefit plan applicable to the most recently hired employees (including future hires if a new benefit formula has been agreed to and communicated to employees). This greatly simplifies administration and accounting; as well as resulting in the correct service cost for new hires.

<u>SUBSTANTIVE PLAN:</u> As required under GASB 74 and 75, we based the valuation on the substantive plan. The formulation of the substantive plan was based on a review of written plan documents as well as historical information provided by San Mateo CCD regarding practices with respect to employer and employee contributions and other relevant factors.

ECONOMIC ASSUMPTIONS:

Economic assumptions are set under the guidance of Actuarial Standard of Practice 27 (ASOP 27). Among other things, ASOP 27 provides that economic assumptions should reflect a consistent underlying rate of general inflation. For that reason, we show our assumed long-term inflation rate below.

<u>INFLATION</u>: We assumed 2.75% per year used for pension purposes. Actuarial standards require using the same rate for OPEB that is used for pension.

<u>INVESTMENT RETURN / DISCOUNT RATE</u>: We assumed 7% per year net of expenses. This is based on assumed long-term return on plan assets assuming 100% funding through Futuris. We used the "Building Block Method". (See Appendix E, Paragraph 53 for more information).

<u>TREND:</u> We assumed 4% per year. Our long-term trend assumption is based on the conclusion that, while medical trend will continue to be cyclical, the average increase over time cannot continue to outstrip general inflation by a wide margin. Trend increases in excess of general inflation result in dramatic increases in unemployment, the number of uninsured and the number of underinsured. These effects are nearing a tipping point which will inevitably result in fundamental changes in health care finance and/or delivery which will bring increases in health care costs more closely in line with general inflation. We do not believe it is reasonable to project historical trend vs. inflation differences several decades into the future.

<u>PAYROLL INCREASE</u>: We assumed 2.75% per year. Since benefits do not depend on salary (as they do for pensions), using an aggregate payroll assumption for the purpose of calculating the service cost results in a negligible error.

<u>FIDUCIARY NET POSITION (FNP):</u> The following table shows the beginning and ending FNP numbers that were provided by San Mateo CCD.

Fiduciary Net Position as of June 30, 2018

	06/30/2017	06/30/2018
Cash and Equivalents	\$0	\$0
Contributions Receivable	\$0	\$0
June trading	\$206,423	\$161,645
Total Investments	\$97,090,909	\$114,947,488
Capital Assets	\$0	\$0
Total Assets	\$97,297,332	\$115,109,133
Benefits Payable	\$0	\$0
Due to broker	(\$206,423)	(\$161,645)
June expenses incurred	(\$29,290)	(\$34,647)
Total Liabilities	(\$235,712)	(\$196,292)
Fiduciary Net Position	\$97,061,619	\$114,912,841

NON-ECONOMIC ASSUMPTIONS:

Economic assumptions are set under the guidance of Actuarial Standard of Practice 35 (ASOP 35). See Appendix E, Paragraph 52 for more information.

MORTALITY

Participant Type	Mortality Tables
Certificated	2009 CalSTRS Mortality
Classified	2014 CalPERS Active Mortality for Miscellaneous Employees

RETIREMENT RATES

Employee Type	Retirement Rate Tables
Certificated	2009 CalSTRS Retirement Rates
Classified	Hired before 1/1/2013: 2009 CalPERS Retirement Rates for School Employees Hired after 12/31/2012: 2009 CalPERS Retirement Rates for Miscellaneous Employees 2% @ 60 adjusted to minimum retirement age of 52

SERVICE REQUIREMENT

Employee Type	Service Requirement Tables
Certificated	Retirement from applicable retirement system
AFSCME	Retirement from applicable retirement system
Classified	Retirement from applicable retirement system
Classified Management	Retirement from applicable retirement system

COSTS FOR RETIREE COVERAGE

The costs below are those used in the September 26, 2017 valuation for this roll-forward, we used increased costs shown below by the applicable trend rate.

Actuarial Standard of Practice 6 (ASOP 6) provides that, as a general rule, retiree costs should be based on actual claim costs or age-adjusted premiums. This is true even for many medical plans that are commonly considered to be "community-rated." However, ASOP 6 contains a provision – specifically section 3.7.7(c) – that allows use of unadjusted premiums in certain circumstances.

Following are the criteria we applied to San Mateo CCD to determine that it is reasonable to assume that San Mateo CCD's future participation in PEMHCA is likely and that the CalPERS medical program as well as its premium structure are sustainable. (We also have an extensive white paper on this subject that provides a basis for our rationale entirely within the context of ASOP 6. We will make this white paper available upon request.)

- Plan qualifies as a "pooled health plan." ASOP 6 defines a "pooled health plan" as one in which premiums are based at least in part on the claims experience of groups other than the one being valued." Since CalPERS rates are the same for all employers in each region, rates are clearly based on the experience of many groups.
- Rates not based to any extent on the agency's claim experience. As mentioned above, rates are the same for all participating employers regardless of claim experience or size.
- Rates not based to any extent on the agency's demographics. As mentioned above, rates are the same for all participating employers regardless of demographics.
- No refunds or charges based on the agency's claim experience or demographics. The terms of operation of the CalPERS program are set by statute and there is no provision for any refunds and

- charges that vary from employer to employer for any reason. The only charges are uniform administrative charges.
- Plan in existence 20 or more years. Enabling legislation to allow "contracting agencies" to participate in the CalPERS program was passed in 1967. The CalPERS medical plan has been successfully operating for almost 50 years. As far back as we can obtain records, the rating structure has been consistent, with the only difference having been a move to regional rating which is unrelated to age-adjusted rating.
- No recent large increases or decreases in the number of participating plans or enrollment. The CalPERS medical plan has shown remarkably stable enrollment. In the past 10 years, there has been small growth in the number of employers in most years with the maximum being a little over 2% and a very small decrease in one year. Average year over year growth in the number of employers over the last 10 years has been about 0.75% per year. Groups have been consistently leaving the CalPERS medical plan while other groups have been joining with no disruption to its stability.
- Agency is not expecting to leave plan in foreseeable future. The District does not plan to leave CalPERS at present.
- <u>No indication the plan will be discontinued.</u> We are unaware of anything that would cause the CalPERS medical plan to cease or to significantly change its operation in a way that would affect this determination.
- The agency does not represent a large part of the pool. The District is in the CalPERS Bay Area region. Based on the information we have, the District constitutes no more than 1.5% of the Bay Area pool. In our opinion, this is not enough for the District to have a measurable effect on the rates or viability of the Bay Area pool.

Retiree liabilities are based on actual retiree costs. Liabilities for active participants are based on the first year costs shown below. Subsequent years' costs are based on first year costs adjusted for trend and limited by any District contribution caps.

Employee Type	Future Retirees Pre-65	Future Retirees Post-65
AFSCME	Hired < 2/1/88: \$16,387	Hired < 2/1/88: \$10,124
	Hired 2/1/88 to 6/30/95: \$12,298	Hired 2/1/88 to 6/30/95: \$8,613
	Hired > $6/30/95$: \$11,104	Hired $> 6/30/95$: \$7,302
Certificated	Hired < 1/1/87: \$16,387	Hired < 2/1/87: \$10,124
	Hired 2/1/88 to 9/6/93: \$12,298	Hired 2/1/87 to 9/6/93: \$8,613
	Hired > $9/6/93$: \$11,333	Hired > 9/6/93: \$7,670
Certificated Management	Hired < 5/1/87: \$16,387	Hired < 5/1/87: \$10,124
_	Hired 5/1/87 to 6/30/94: \$12,298	Hired 5/1/87 to 6/30/94: \$8,613
	Hired > $6/30/94$: \$11,333	Hired $> 6/30/94$: \$7,670
Classified	Hired < 5/1/87: \$16,387	Hired < 5/1/87: \$10,124
	Hired 5/1/87 to 6/30/94: \$12,298	Hired 5/1/87 to 6/30/94: \$8,613
	Hired > $6/30/94$: \$11,104	Hired $> 6/30/94$: \$7,302
Classified Management	Hired < 5/1/87: \$16,387	Hired < 5/1/87: \$10,124
_	Hired 5/1/87 to 6/30/94: \$12,298	Hired 5/1/87 to 6/30/94: \$8,613
	Hired > 6/30/94: \$11,104	Hired $> 6/30/94$: \$7,302

PARTICIPATION RATES

Employee Type	<65 Non-Medicare Participation %	65+ Medicare Participation %
Certificated	100%	100%
Classified	100%	100%

TURNOVER

Employee Type	Turnover Rate Tables
Certificated	2009 CalSTRS Termination Rates
Classified	2009 CalPERS Termination Rates for School Employees

SPOUSE PREVALENCE

To the extent not provided and when needed to calculate benefit liabilities, 80% of retirees assumed to be married at retirement. After retirement, the percentage married is adjusted to reflect mortality.

SPOUSE AGES

To the extent spouse dates of birth are not provided and when needed to calculate benefit liabilities, female spouse assumed to be three years younger than male.

APPENDIX D: DISTRIBUTION OF ELIGIBLE PARTICIPANTS BY AGE

ELIGIBLE ACTIVE EMPLOYEES

			Certificated			Classified
Age	Total	AFSCME	Management	Faculty	Classified	Management
Under 25	5	1	0	0	3	1
25-29	53	5	0	2	40	6
30-34	108	6	3	25	62	12
35-39	127	14	5	44	45	19
40-44	103	9	7	36	29	22
45-49	119	13	5	49	29	23
50-54	123	11	13	45	36	18
55-59	128	16	6	44	46	16
60-64	104	11	7	38	30	18
65 and older	77	1	8	39	19	10
Total	947	87	54	322	339	145

ELIGIBLE RETIREES

			Certificated			Classified
Age	Total	AFSCME	Management	Faculty	Classified	Management
Under 50	0	0	0	0	0	0
50-54	1	0	0	0	0	1
55-59	16	10	0	2	1	3
60-64	49	0	1	14	28	6
65-69	77	2	2	44	22	7
70-74	131	0	2	64	60	5
75-79	128	0	0	84	44	0
80-84	113	0	0	64	46	3
85-89	95	0	0	47	46	2
90 and older	76	0	0	22	50	4
Total	686	12	5	341	297	31

APPENDIX E: GASB 74/75 ACCOUNTING ENTRIES AND DISCLOSURES

This report does not necessarily include the entire accounting values. As mentioned earlier, there are certain deferred items that are employer-specific. The District should consult with its auditor if there are any questions about what, if any, adjustments may be appropriate.

GASB 74/75 include a large number of items that should be included in the Note Disclosures and Required Supplementary Information (RSI) Schedules. Many of these items are outside the scope of the actuarial valuation. However, following is information to assist the District in complying with GASB 74/75 disclosure requirements:

Paragraph 50: Information about the OPEB Plan

Most of the information about the OPEB plan should be supplied by San Mateo CCD. Following is information to help fulfill Paragraph 50 reporting requirements.

50.c: Following is a table of plan participants

	Number of Participants
Inactive Employees Receiving Benefits	686
Inactive Employees Entitled to But Not Receiving Benefits*	0
Participating Active Employees	947
Total Number of participants	1633

*We were not provided with information about any terminated, vested employees

Paragraph 51: Significant Assumptions and Other Inputs

shown in Appendix C.

Paragraph 52:

Information Related to Assumptions and Other Inputs

The following information is intended to assist San Mateo CCD in complying with the requirements of Paragraph 52.

52.b: <u>Mortality Assumptions</u> Following are the tables the mortality assumptions are based upon. Inasmuch as these tables are based on appropriate populations, and that these tables are used for pension purposes, we believe these tables to be the most appropriate for the valuation.

Mortality Table	2009 CalSTRS Mortality	
Disclosure	The mortality assumptions are based on the 2009 CalSTRS	
	Mortality table created by CalSTRS. CalSTRS periodically	
	studies mortality for participating agencies and establishes	
	mortality tables that are modified versions of commonly used	
	tables. This table incorporates mortality projection as deemed	
	appropriate based on CalSTRS analysis.	

Mortality Table	2014 CalPERS Retiree Mortality for Miscellaneous Employees		
Disclosure	The mortality assumptions are based on the 2014 CalPERS		
	Retiree Mortality for Miscellaneous Employees table created by		
	CalPERS. CalPERS periodically studies mortality for		
	participating agencies and establishes mortality tables that are		
	modified versions of commonly used tables. This table		
	incorporates mortality projection as deemed appropriate based on		
	CalPERS analysis.		
Mortality Table	2014 CalPERS Active Mortality for Miscellaneous Employees		
Disclosure	The mortality assumptions are based on the 2014 CalPERS		
	Active Mortality for Miscellaneous Employees table created by		
	CalPERS. CalPERS periodically studies mortality for		
	participating agencies and establishes mortality tables that are		
	modified versions of commonly used tables. This table		
	incorporates mortality projection as deemed appropriate based on		
	CalPERS analysis.		

52.c: <u>Experience Studies</u> Following are the tables the retirement and turnover assumptions are based upon. Inasmuch as these tables are based on appropriate populations, and that these tables are used for pension purposes, we believe these tables to be the most appropriate for the valuation.

Retirement Tables

г	·		
Retirement Table	2009 CalSTRS Retirement Rates		
Disclosure	The retirement assumptions are based on the 2009 CalSTRS		
	Retirement Rates table created by CalSTRS. CalSTRS		
	periodically studies the experience for participating agencies and		
	establishes tables that are appropriate for each pool.		
Retirement Table	2009 CalPERS 2.0% @60 Rates for Miscellaneous Employees		
Disclosure	The retirement assumptions are based on the 2009 CalPERS		
	2.0% @60 Rates for Miscellaneous Employees table created by		
	CalPERS. CalPERS periodically studies the experience for		
	participating agencies and establishes tables that are appropriate		
	for each pool.		
Retirement Table	2009 CalPERS Retirement Rates for School Employees		
Disclosure	The retirement assumptions are based on the 2009 CalPERS		
	Retirement Rates for School Employees table created by		
	CalPERS. CalPERS periodically studies the experience for		
	participating agencies and establishes tables that are appropriate		
	for each pool.		

Turnover Tables

Turnover Table	2009 CalSTRS Termination Rates	
Disclosure	The turnover assumptions are based on the 2009 CalSTRS	
	Termination Rates table created by CalSTRS. CalSTRS	
	periodically studies the experience for participating agencies and	
	establishes tables that are appropriate for each pool.	

Turnover Table	2009 CalPERS Termination Rates for School Employees
Disclosure	The turnover assumptions are based on the 2009 CalPERS
	Termination Rates for School Employees table created by
	CalPERS. CalPERS periodically studies the experience for
	participating agencies and establishes tables that are appropriate
	for each pool.

For other assumptions, we use actual plan provisions and plan data.

52.d: The alternative measurement method was not used in this valuation.

52.e: <u>NOL Using alternative trend assumptions</u> The following table shows the Net OPEB Liability with a health care cost trend rate 1% higher and 1% lower than assumed in the valuation.

	Trend 1% Lower	Valuation Trend	Trend 1% Higher
Net OPEB Liability	(\$11,867,708)	\$6,150,492	\$28,575,126

Paragraph 53:

Discount Rate

The following information is intended to assist San Mateo CCD to comply with Paragraph 53 requirements.

- 53.a: A discount rate of 7% was used in the valuation.
- 53.b: We assumed that contributions would be sufficient to fully fund the obligation over a period not to exceed 30 years.
- 53.c: We used historic 28 year real rates of return for each asset class along with our assumed long-term inflation assumption to set the discount rate. We offset the expected investment return by investment expenses of 25 basis points.
- 53.d and 53.e.: Not applicable.

53.f: Following is the assumed asset allocation and assumed rate of return for each. Futuris - Custom San Mateo CCD

Asset Class	Percentage of Portfolio	Assumed Gross Return
Fixed Income	25%	4%
Equities	75%	8%

We looked at rolling periods of time for all asset classes in combination to appropriately reflect correlation between asset classes. That means that the average returns for any asset

class don't necessarily reflect the averages over time individually, but reflect the return for the asset class for the portfolio average. We used geometric means.

53.g: The following table shows the Net OPEB liability with a discount rate 1% higher and 1% lower than assumed in the valuation.

	Discount Rate	Valuation	Discount Rate
	1% Lower	Discount Rate	1% Higher
Net OPEB Liability	\$19,336,881	\$6,150,492	(\$4,923,225)

Paragraph 55:

Changes in the Net OPEB Liability

Please see reconciliation on page 10. Please see the notes for Paragraph 244 below for more information.

Paragraph 56:

Additional Net OPEB Liability Information

The following information is intended to assist San Mateo CCD to comply with Paragraph 56 requirements.

56.a: The valuation date is June 30, 2017.

The measurement date is June 30, 2018.

56 b; 56 c; 56.d; 56.e; 56.f: Not applicable

56.g: To be determined by the employer

56.h.(1) through (4): Not applicable

56.h.(5): To be determined by the employer

56.i: Not applicable

Paragraph 57:

Required Supplementary Information

- 57.a: Please see reconciliation on page 10. Please see the notes for Paragraph 244 below for more information.
- 57.b: These items are provided on page 10 for the current valuation, except for covered payroll, which should be determined based on appropriate methods.
- 57.c: We have not been asked to calculate an actuarially determined contribution amount. We assume the District contributes on an ad hoc basis, but in an amount sufficient to fully fund the obligation over a period not to exceed 28 years.
- 57.d: We are not aware that there are any statutorily or contractually established contribution requirements.

Paragraph 58:

Actuarially Determined Contributions

We have not been asked to calculate an actuarially determined contribution amount. We assume the District contributes on an ad hoc basis, but in an amount sufficient to fully fund the obligation over a period not to exceed 28 years.

Paragraph 244: Transition Option

Prior periods were not restated due to the fact that prior valuations were not rerun in accordance with GASB 75. It was determined that the time and expense necessary to rerun prior valuations and to restate prior financial statements was not justified.

APPENDIX F: DEFERRED OUTFLOWS OF RESOURCES AND DEFERRED INFLOWS OF RESOURCES

EXPERIENCE GAINS AND LOSSES

Increase (Decrease) in OPEB Expense Arising from the Recognition of Effects of Experience Gains and Losses (Measurement Periods)

Measurement Period	Experience Gain/Loss	Original Recognition Period (Years)	Amounts Recognized in OPEB Expense through 2017	2018	Amounts to be Recognized in OPEB Expense after 2018	2019	2020	2021	2022	2023	Thereafter
2017-18	\$0	0	\$0	\$0	\$0						
Net Increase (Decrease) in OPEB Expense		EB Expense	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

CHANGES OF ASSUMPTIONS

Increase (Decrease) in OPEB Expense Arising from the Recognition of Effects of Changes of Assumptions (Measurement Periods)

Measurement Period	Changes of Assumptions	Original Recognition Period (Years)	Amounts Recognized in OPEB Expense through 2017	2018	Amounts to be Recognized in OPEB Expense after 2018	2019	2020	2021	2022	2023	Thereafter
2017-18	\$0	0	\$0	\$0	\$0						
Net Increase (Decrease) in OPEB Expense		B Expense	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

INVESTMENT GAINS AND LOSSES

Increase (Decrease) in OPEB Expense Arising from the Recognition of Effects of Investment Gains and Losses (Measurement Periods)

Measurement Period	Investment Gain/Loss	Original Recognition Period (Years)	Amounts Recognized in OPEB Expense through 2017	2018	Amounts to be Recognized in OPEB Expense after 2018	2019	2020	2021	2022	2023	Thereafter
2017-18	\$1,180,091	5	\$0	\$236,019	\$944,072	\$236,019	\$236,019	\$236,019	\$236,015		
Net Increase (Decrease) in OPEB Expense		B Expense	\$0	\$236,019	\$944,072	\$236,019	\$236,019	\$236,019	\$236,015	\$0	\$0

APPENDIX G: GLOSSARY OF RETIREE HEALTH VALUATION TERMS

Note: The following definitions are intended to help a *non*-actuary understand concepts related to retiree health

valuations. Therefore, the definitions may not be actuarially accurate.

Actuarial Cost Method: A mathematical model for allocating OPEB costs by year of service. The only

actuarial cost method allowed under GASB 74/75 is the entry age actuarial cost

method.

Actuarial Present Value of

Projected Benefit Payments: The projected amount of all OPEB benefits to be paid to current and future retirees

discounted back to the valuation or measurement date.

Deferred Inflows/Outflows

of Resources: A portion of certain items that can be deferred to future periods or that weren't

reflected in the valuation. The former includes investment gains/losses, actuarial gains/losses, and gains/losses due to changes in actuarial assumptions or methods. The latter includes contributions made to a trust subsequent to the measurement

date but before the statement date.

<u>Discount Rate:</u> Assumed investment return net of all investment expenses. Generally, a higher

assumed interest rate leads to lower service costs and total OPEB liability.

Fiduciary Net Position: Net assets (liability) of a qualifying OPEB "plan" (i.e. qualifying irrevocable trust

or equivalent arrangement).

<u>Implicit Rate Subsidy:</u> The estimated amount by which retiree rates are understated in situations where,

for rating purposes, retirees are combined with active employees and the employer

is expected, in the long run, to pay the underlying cost of retiree benefits.

Measurement Date: The date at which assets and liabilities are determined in order to estimate TOL and

NOL.

Mortality Rate: Assumed proportion of people who die each year. Mortality rates always vary by

age and often by sex. A mortality table should always be selected that is based on

a similar "population" to the one being studied.

Net OPEB Liability (NOL): The Total OPEB Liability minus the Fiduciary Net Position.

OPEB Benefits: Other Post Employment Benefits. Generally medical, dental, prescription drug,

life, long-term care or other postemployment benefits that are not pension benefits.

OPEB Expense: This is the amount employers must recognize as an expense each year. The annual

OPEB expense is equal to the Service Cost plus interest on the Total OPEB Liability (TOL) plus change in TOL due to plan changes minus projected investment income; all adjusted to reflect deferred inflows and outflows of

resources.

<u>Participation Rate:</u> The proportion of retirees who elect to receive retiree benefits. A lower

participation rate results in lower service cost and a TOL. The participation rate

often is related to retiree contributions.

<u>Retirement Rate:</u> The proportion of active employees who retire each year. Retirement rates are

usually based on age and/or length of service. (Retirement rates can be used in conjunction with the service requirement to reflect both age and length of service). The more likely employees are to retire early, the higher service costs and actuarial

accrued liability will be.

Service Cost: The annual dollar value of the "earned" portion of retiree health benefits if retiree

health benefits are to be fully accrued at retirement.

<u>Service Requirement:</u> The proportion of retiree benefits payable under the OPEB plan, based on length of

service and, sometimes, age. A shorter service requirement increases service costs

and TOL.

<u>Total OPEB Liability (TOL):</u> The amount of the actuarial present value of projected benefit payments

attributable to employees' past service based on the actuarial cost method used.

Trend Rate: The rate at which the employer's share of the cost of retiree benefits is expected to

increase over time. The trend rate usually varies by type of benefit (e.g. medical, dental, vision, etc.) and may vary over time. A higher trend rate results in higher

service costs and TOL.

<u>Turnover Rate:</u> The rate at which employees cease employment due to reasons other than death,

disability or retirement. Turnover rates usually vary based on length of service and may vary by other factors. Higher turnover rates reduce service costs and TOL.

Valuation Date: The date as of which the OPEB obligation is determined by means of an actuarial

valuation. Under GASB 74 and 75, the valuation date does not have to coincide

with the statement date, but can't be more than 30 months prior.