

RFP#15/RFP#13

RFP 18
FILE NO. 43-C1
APPL. NO. 01-110074

RESTROOM SIDE

INTERIOR PLUMBING WALL - 1 HR. RATED
1/4" CERAMIC TILE ON LATEX THINSET ADHESIVE
INSTALLED OVER (2) LAYERS 5/8" TYPE "X"
MOISTURE-RESISTANT GYP. BD. OVER 6" STUDS 16 GA
AT 16" O.C. TOP ON THE RESTROOM SIDE AND (3)
LAYER 5/8" TYPE "X" GYP. BD. ON THE OTHER SIDE.
INSTALL ALL GYP. BD. TO UNDERSIDE OF DECK ABOVE.
SOUND INSULATION IN STUD CAVITY, U.S.A.
CA FILE #WP 1072

HEAD DETAIL: 16/A10.52
SILL DETAIL: 16/A10.52

REF: A10.51 RFP 18

SCALE: 1-1/2" = 1'-0"

1 WALL TYPE P3

RESTROOM SIDE

INTERIOR PLUMBING WALL - 1 HR. RATED
1/4" CERAMIC TILE ON LATEX THINSET ADHESIVE
INSTALLED OVER (1) LAYER 5/8" TYPE "X"
MOISTURE-RESISTANT GYP. BD. OVER 4" STUDS 16 GA
AT 16" O.C. 1/2" AIR GAP ADJACENT TO (6) CONC.
WALL. INSTALL ALL GYP. BD. TO UNDERSIDE OF DECK
ABOVE. SOUND INSULATION IN STUD CAVITY, U.S.A.
HEAD DETAIL: 16/A10.52
SILL DETAIL: 16/A10.52

REF: NEW DETAIL

SCALE: 1-1/2" = 1'-0"

2 WALL TYPE P6

