DOOR SCHEDULE / HARDWARE SCHEDULE

MARK	TYPE	SIZE	THICK-NESS	MATERIAL	FINISH	FRAME MATL.	FRAME FINISH	FRAME HEAD	FRAME JAMB	FRAME SILL	FIRE RATING	GLASS	REMARKS	HANG DOOR	SECURE DOOR INACTIVE LEAF	SECURE DOOR ACTIVE LEAF	PUSH/ PULL	ACCES-SORIES (PAIRS)	CLOSE DOOR	PROTECT DOOR	STOP/ HOLDER	WEATHER-STRIPPING PERI-METER	WEATHER-STRIPPING SILL	WEATHER-STRIPPING HEAD	THRESH-OLD	OTHER HARDWARE/ REMARKS
GROUND FLOOR																										
101	H	PAIR 3'-0" x 7'-10"	1 3/4"	ALUM	ANODIZED	ALUM	ANODIZE	9N/A8.1 SIM	9N/A8.1 SIM	1A/A8.1 SIM	–	TEMPERED	REMOVE (E) DOOR VERIFY DOOR SIZE IN FIELD	SELECT SL26HD	VD99 EL, NL	VD 99 EL E0	VD 392-7	–	SEE NOTE 1	–	FS444	316DS	MFGR STD WS	–	229D	1 MFGR'S STD WS AT MEETING STILES
102	A	PAIR 3'-0" x 7'-0"	1 3/4"	SCW	PAINT	(E) STEEL	PAINT	–	–	–	1-1/2 HR	WIRE		(E)	9947WDC-DT	9947WDC-NL	–	–	4040	–	FS436	S88	4131DRL	–	272D	2 4 7
103	D	PAIR 3'-0" x 7'-10"	1 3/4"	ALUM	ANODIZED	ALUM	ANODIZED	1U/A8.1	9N/A8.1	1A/A8.1	–	TEMPERED	REMOVE (E) DOOR VERIFY DOOR SIZE IN FIELD	SELECT SL26HD	VD99 EL, NL	VD 99 EL E0	VD 392-7	–	SEE NOTE 1A	–	IVES FS444	316DS	MFGR STD WS	–	229D	1A MFGR'S STD WS AT MEETING STILES
104	NOT USED																									
105	B	PAIR 3'-0" x 7'-0"	1 3/4"	SCW	PAINT	STEEL	PAINT	1H/A8.1	1H/A8.1	METAL TRANSITION STRIP	20 MIN	WIRE	REMOVE (E) DOOR AND FRAME VERIFY (E) R.O. IN FIELD	BB1168	9947WDC-EO-F	9947WDC-L	–	PEMKO 297DS	4040	KICK	FS436	S88	–	–	–	5 7
106	(E) A	3'-0" x 7'-0"	1 3/4"	(E) SCW	–	(E) STEEL	–	–	–	–	20 MIN	WIRE	SEE SEISMIC REHABILITATION SCOPE OF WORK	(E) BB1168	–	(E) D70PD	–	–	(E) 4040	(E) KICK	FS436	(E) S88	–	–	–	2 7
107	A	3'-0" x 7'-0"	1 3/4"	SCW	PAINT	STEEL	PAINT	1H/A8.1	1H/A8.1	–	20 MIN	WIRE	REMOVE (E) DOOR AND FRAME VERIFY (E) R.O. IN FIELD	BB1168	–	D70PD	–	–	4040	KICK	FS436	S88	–	–	–	2 7
108	(E) A	3'-0" x 7'-0"	1 3/4"	(E) SCW	–	(E) STEEL	–	–	–	METAL TRANSITION STRIP	20 MIN.	WIRE	REMOVE (E) DOOR AND FRAME VERIFY (E) R.O. IN FIELD	BB1168	–	D70PD	–	–	4040	KICK	FS436	S88	–	–	–	5 7
109	J	PAIR 3'-0" x 7'-0"	1 3/4"	SCW	PAINT	STEEL	PAINT	1A/A8.4 SIM	1A/A8.4	METAL TRANSITION STRIP	20 MIN	WIRE	SEE SEISMIC REHABILITATION SCOPE OF WORK	(E) BB1168	(E) GJ FB41P	(E) D70PD	–	(E) PEMKO 355DS	(E) 4040	(E) KICK	FS436	(E) S88	–	–	–	5 7
110	NOT USED																									
111	C	PAIR 3'-0" x 7'-0"	1 3/4"	SCW	PAINT	STEEL	PAINT	1H/A8.1	1H/A8.1	–	1 HR	–	REMOVE (E) DOOR AND FRAME VERIFY (E) R.O. IN FIELD	BB1279	GJ FB41P	D80PD	–	PEMKO 355DS	4040	KICK	FS436	S88	–	–	–	3 7
112	A	3'-0" x 7'-0"	1 3/4"	SCW	PAINT	STEEL	PAINT	1H/A8.1	1H/A8.1	–	20 MIN	WIRE	REMOVE (E) DOOR AND FRAME VERIFY (E) R.O. IN FIELD	BB1168	–	D70PD	–	–	4040	KICK	FS436	S88	–	–	–	5 7
113	A	3'-0" x 7'-0"	1 3/4"	SCW	PAINT	STEEL	PAINT	1H/A8.1	1H/A8.1	–	20 MIN.	WIRE	REMOVE (E) DOOR AND FRAME VERIFY (E) R.O. IN FIELD	BB1168	–	D70PD	–	–	4040	KICK	FS436	S88	–	–	–	5 7
114	C	2'-8" x 7'-0"	1 3/4"	SCW	PAINT	STEEL	PAINT	1H/A8.1	1H/A8.1	–	20 MIN.	–	REMOVE (E) DOOR AND FRAME VERIFY (E) R.O. IN FIELD	BB1279	–	D80PD	–	–	4040	KICK	FS436	S88	–	–	–	7
115	C	3'-0" x 7'-0"	1 3/4"	SCW	PAINT	GALV STEEL	PAINT	1H/A8.1	1H/A8.1	–	20 MIN.	–	REMOVE (E) DOOR AND FRAME VERIFY (E) R.O. IN FIELD	BB1168	–	S210PD	–	–	4040	ARMOR	FS436	S88	–	–	–	
116	C	2'-8" x 7'-0"	1 3/4"	SCW	PAINT	STEEL	PAINT	1H/A8.1	1H/A8.1	–	20 MIN.	–	REMOVE (E) DOOR AND FRAME VERIFY (E) R.O. IN FIELD	BB1279	–	D80PD	–	–	4040	ARMOR	FS436	S88	–	–	–	7
117	C	3'-0" x 7'-0"	1 3/4"	SCW	PAINT	GALV STEEL	PAINT	1H/A8.1	1H/A8.1	–	20 MIN.	–	REMOVE (E) DOOR AND FRAME VERIFY (E) R.O. IN FIELD	BB1168	–	S210PD	–	–	4040	ARMOR	FS436	S88	–	–	–	
118	A	3'-0" x 7'-0"	1 3/4"	SCW	PAINT	STEEL	PAINT	1H/A8.1	1H/A8.1	–	20 MIN.	WIRE	REMOVE (E) DOOR AND FRAME VERIFY (E) R.O. IN FIELD	BB1168	–	D70PD	–	–	4040	KICK	FS436	S88	–	–	–	2 7
119	A	3'-0" x 7'-0"	1 3/4"	SCW	PAINT	STEEL	PAINT	1H/A8.1	1H/A8.1	–	20 MIN.	WIRE	REMOVE (E) DOOR AND FRAME VERIFY (E) R.O. IN FIELD	BB1168	–	D70PD	–	–	4040	KICK	FS436	S88	–	–	–	2 7
120	NOT USED																									
121	C	2'-8" x 7'-0"	1 3/4"	SCW	PAINT	STEEL	PAINT	1H/A8.1	1H/A8.1	–	20 MIN.	–	REMOVE (E) DOOR AND FRAME VERIFY (E) R.O. IN FIELD	BB1279	–	D80PD	–	–	4040	KICK	FS436	S88	–	–	–	7
122	NOT USED																									7
123	B	3'-0" x 7'-0"	1 3/4"	SCW	PAINT	STEEL	PAINT	25U/A8.1	25U/A8.1	–	–	TEMPERED	–	BB1279	–	D93PD	–	–	–	KICK	FS436	–	–	–	–	7
124	B	3'-0" x 7'-0"	1 3/4"	SCW	PAINT	STEEL	PAINT	18H/A8.1	18H/A8.1	–	–	TEMPERED	–	BB1279	–	D70PD	–	–	–	KICK	FS436	–	–	–	–	7
125	B	3'-0" x 7'-0"	1 3/4"	SCW	PAINT	STEEL	PAINT	18H/A8.1	18H/A8.1	–	–	TEMPERED	–	BB1279	–	D70PD	–	–	–	KICK	FS436	–	–	–	–	7
126	C	2'-8" x 7'-0"	1 3/4"	SCW	PAINT	GALV STEEL	PAINT	18H/A8.1 SIM	18H/A8.1 SIM	–	–	–	REMOVE (E) DOOR AND FRAME VERIFY (E) R.O. IN FIELD	BB1279	–	D80PD	–	–	–	ARMOR	FS436	–	–	–	–	7
127	B	3'-0" x 7'-0"	1 3/4"	SCW	PAINT	STEEL	PAINT	25U/A8.1 SIM	25U/A8.1 SIM	–	–	TEMPERED		BB1279	–	D93PD	–	–	–	KICK	FS436	–	–	–	–	7
128	B	PAIR 3'-0" x 7'-0"	1 3/4"	SCW	PAINT	STEEL	PAINT	25U/A8.1 SIM	25U/A8.1 SIM	–	–	TEMPERED		BB1279	GJ FB41P	D93PD (NORTH DOOR)	–	–	–	KICK	FS436	–	–	–	–	FLUSH BOLT ON SOUTH DOOR 7
129	(E) C	3'-0" x 7'-0"	1 3/4"	(E) STEEL	(E)	(E) STEEL	(E)	–	–	–	–	–	(E) DOOR, FRAME AND HARDWARE	(E)	–	(E)	–	–	–	–	(E)	–	–	–	–	7
130	NOT USED																									
131	B	3'-0" x 7'-0"	1 3/4"	SCW	PAINT	STEEL	PAINT	18H/A8.1	18H/A8.1	–	–	TEMPERED		BB1279	–	D70PD	–	–	–	KICK	FS436	–	–	–	–	7
132	B	3'-0" x 7'-0"	1 3/4"	SCW	PAINT	STEEL	PAINT	16A/A8.1 SIM	16A/A8.1	–	–	TEMPERED		BB1279	–	D70PD	–	–	–	KICK	FS436	–	–	–	–	7
133	B	3'-0" x 7'-0"	1 3/4"	SCW	PAINT	STEEL	PAINT	16A/A8.1 SIM	16A/A8.1	–	–	TEMPERED		BB1279	–	D93PD	–	–	–	KICK	FS436	–	–	–	–	– 7
FIRST FLOOR																										
201	H	PAIR 3'-0" x 7'-10"	1 3/4"	ALUM	ANODIZED	ALUM	ANODIZE	9N/A8.1 SIM	9N/A8.1 SIM	1A/A8.1 SIM	–	TEMPERED	REMOVE (E) DOOR VERIFY DOOR SIZE IN FIELD	SELECT SL26HD	VD99 EL, NL	VD 99 EL E0	VD 392-7	–	SEE NOTE 1	(E)	FS444	316DS	MFGR STD WS	–	229D	1 MFGR'S STD WS AT MEETING STILES
202	A	PAIR 3'-0" x 7'-0"	1 3/4"	SCW	PAINT	(E) STEEL	PAINT	–	–	–	1-1/2 HR	WIRE		(E)	9947WDC-DT	9947WDC-NL	–	–	4040	–	FS436	S88	4131DRL	–	272D	2 4 7
203	D	PAIR 3'-0" x 7'-10"	1 3/4"	ALUM	ANODIZED	ALUM	ANODIZED	1U/A8.1	9N/A8.1	1A/A8.1	–	TEMPERED	REMOVE (E) DOOR VERIFY DOOR SIZE IN FIELD	SELECT SL26HD	VD99 EL, NL	VD 99 EL E0	VD 392-7	–	SEE NOTE 1A	–	IVES FS444	316DS	MFGR STD WS	–	229D	1A MFGR'S STD WS AT MEETING STILES
204	NOT USED																									
205	NOT USED																									
206	NOT USED																									
207	B	3'-0" x 7'-0"	1 3/4"	SCW	PAINT	HW	PAINT	–	–	–	–	–	REMOVE (E) DOOR VERIFY DOOR SIZE IN FIELD	BB1168	–	D70PD	–	–	FS436	KICK	FS436	S88	–	–	–	
208	A	3'-0" x 7'-0"	1 3/4"	SCW	PAINT	(E) STEEL	PAINT	–	–	–	20 MIN.	WIRE	–	BB1168	–	D70PD	–	–	FS436		(E)	S88	–	–	–	2 7
209	A	3'-0" x 7'-0"	1 3/4"	SCW	PAINT	(E) STEEL	PAINT	–	–	–	20 MIN.	WIRE	–	BB1168	–	D70PD	–	–	FS436		(E)	S88	–	–	–	2 7
210	NOT USED																									
211	C	2'-8" x 7'-0"	1 3/4"	SCW	PAINT	STEEL	PAINT	18H/A8.1 SIM	18H/A8.1	–	–	–	VERIFY DOOR SIZE IN FIELD	BB1279	–	D80PD	–	–	–	ARMOR	FS436	–	–	–	–	7
212	C	3'-0" x 7'-0"	1 3/4"	SCW	PAINT	(E) STEEL	PAINT	–	–	–	20 MIN.	–	VERIFY DOOR SIZE IN FIELD	BB1279	–	D80PD	–	–	4040	–	FS436	(E)	–	–	–	7
213	C	3'-0" x 7'-0"	1 3/4"	SCW	PAINT	STEEL	PAINT	1H/A8.1	1H/A8.1	–	20 MIN	–	(N) DOOR, FRAME AND HARDWARE	BB1168	–	S210PD	–	–	4040	ARMOR	FS436	S88	–	–	–	7
214	C	2'-8" x 7'-0"	1 3/4"	SCW	PAINT	(E) STEEL	PAINT	–	–	–	20 MIN.			BB1279	–	99L-F	–	–	4040	ARMOR	FS436	S88	–	–	–	7
215	A	PAIR 3'-0" x 7'-0"	1 3/4"	SCW	PAINT	(E) STEEL	PAINT	–	–	–	20 MIN	–		BB1279	–	99L-F	–	–	4040	–	FS436	S88	–	–	–	2 7
216	C	3'-0" x 7'-0"	1 3/4"	SCW	PAINT	STEEL	PAINT	1H/A8.1	1H/A8.1	–	20 MIN	–	REMOVE (E) DOOR AND FRAME	BB1168	–	S210PD	–	–	4040	ARMOR	(E)	S88	–	–	–	7
217	(E)	2'-8" x 7'-0"	1 3/4"	(E) SCW	PAINT	(E) STEEL	PAINT	–	–	–	(E) 20 MIN	–	REMOVE (E) LOCKSET AND CLOSER	(E)	–	D80PD	–	–	4040	–	FS436	S88	–	–	–	7
218	C	3'-0" x 7'-0"	1 3/4"	SCW	PAINT	(E) STEEL	PAINT	–	–	–	1-1/2HR	–		(E)	–	D70PD	–	–	4040	–	FS436	S88	–	–	–	2 7
221	C	3'-0" x 7'-0"	1 3/4"	SCW	PAINT	(E) STEEL	PAINT	–	–	–	(E) 20 MIN.	–		(E)	–	99L-F	–	–	4040	–	FS436	S88	–	–	–	7
222	A	2'-8" x 7'-0"	1 3/4"	SCW	PAINT	(E) STEEL	PAINT	–	–	–	–	–	REMOVE (E) LOCKSET AND CLOSER	(E)	–	D80PD	–	–	–	–	FS436	–	–	–	–	7
223	NOT USED																									
224	A	3'-0" x 7'-0"	1 3/4"	SCW	PAINT	(E) STEEL	PAINT	–	–	–	–	–	REMOVE (E) LOCKSET AND CLOSER	(E)	–	99L-F	–	–	4040	–	FS436	–	–	–	–	7
225	A	3'-0" x 7'-0"	1 3/4"	SCW	PAINT	STEEL	PAINT	–	–	–	20 MIN.	WIRE		BB1168	–	99L-F	–	–	4040	–	FS436	S88	–	–	–	2 7
226	A	3'-0" x 7'-0"	1 3/4"	SCW	PAINT	(E) STEEL	PAINT	–	–	–	20 MIN.	WIRE		BB1168	–	99L-F	–	–	4040	–	FS436	S88	–	–	–	2 7
231	(E) A	3'-0" x 7'-0"	1 3/4"	(E) SCW	(E)	(E) STEEL	(E)	–	–	–	(E) 20 MIN.	(E) WIRE	(E) DOOR, FRAME AND HARDWARE	BB1168	–	99L-F	–	–	(E)	–	(E) FS436	(E) S88	–	–	–	2 7
232	(E) A	3'-0" x 7'-0"	1 3/4"	(E) SCW	(E)	(E) STEEL	(E)	–	–	–	(E) 20 MIN.	(E) WIRE	(E) DOOR, FRAME AND HARDWARE	BB1168	–	D70PD	–	–	(E)	–	(E)	(E)	–	–	–	2 7
233	(E) A	3'-0" x 7'-0"	1 3/4"	(E) SCW	(E)	(E) STEEL	(E)	–	–	–	(E) 20 MIN.	(E) WIRE	(E) DOOR, FRAME AND HARDWARE	BB1168	–	D70PD	–	–	(E)	–	(E)	(E)	–	–	–	2 7
234	(E) A	3'-0" x 7'-0"	1 3/4"	(E) SCW	(E)	(E) STEEL	(E)	–	–	–	(E) 20 MIN.	WIRE	(E) DOOR, FRAME AND HARDWARE	(E) BB1168	–	(E) 99L-F	–	–	(E) 4040	(E) KICK	(E) FS436	(E) S88	–	–	–	2 7
235	NOT USED																									
236	(E) C	3'-0" x 7'-0"	(E) 1 3/4"	(E) SCW	(E) PAINT	(E) STEEL	(E)	–	–	–	–	–	–	(E) BB1279	–	(E) D40S	–	–	–	(E) KICK	(E) GJ FB-36	–	–	–		

NOTE: SEE SHEET A4.3 FOR DOOR TYPE, SHEET NOTES FOR DOOR & HARDWARE, ABBREVIATION AND DOORS & HARDWARE SCHEDULE KEY NOTES.

REVISION	DESCRIPTION	INITIAL	DATE
1	ADDENDUM	TKB	4/1/04
	PRE-APPLICATION REVIEW		02/06/04
	ISSUED FOR PLAN CHECK		03/03/04
	ISSUED FOR PERMIT		03/03/04
	ISSUED FOR BID		
	ISSUED FOR CONSTRUCTION		

SEAL: LICENSED ARCHITECT THOMAS K. BUTT No. C 7,389 REN. 3-31-07 STATE OF CALIFORNIA

CONSULTANT:

INTERACTIVE RESOURCES
ARCHITECTURE • PLANNING • ENGINEERING
117 PARK PLACE
POINT RICHMOND
CALIFORNIA 94801
(510) 236-7435
(FAX) 232-5325
http//www.intres.com

PROJECT:

BUILDING NO. 18 (NORTH HALL) MODERNIZATION

COLLEGE OF SAN MATEO
1700 WEST HILLSDALE BLVD.
SAN MATEO, CA 94402

SAN MATEO CO. COMMUNITY COLLEGE DISTRICT

IDENTIFICATION STAMP
DIV. OF THE STATE ARCHITECT
OFFICE OF REGULATION SERVICES
APPL 106047
AC ____ FLS ____ SS ____
DATE ____

APPROVED
DIV. OF THE STATE ARCHITECT
APPL 106047
AC ____ FLS ____ SS ____
DATE ____

SHEET TITLE:

DOOR AND HARDWARE SCHEDULE

PROJ. NO. 2002-066.02
PREPARATION AND REVIEW
DRAWN BY BA
DESIGNER TKB
PROJ. MGR. TKB
PEER REVIEW

SHEET NUMBER:

MOD A4.2

NUMBER: OF: