



1 LEVEL 2 FLOOR PLAN  
3/32" = 1'-0"

**NOTES**

- REFER TO SPECIFICATION SECTION 90020 FOR INTERIOR FINISH FOR REFERENCE FOR ALL FINISH DESIGNATIONS.
- ACCENT WALL SHALL BE EGGSHELL FINISH ONLY.
- ALL DOOR FRAMES TO BE PAINTED WITH ADJACENT WALL COLOR. SOLID IN SEMI-GLOSS, U.O.N.
- FLOOR FINISH TRANSITIONS TO BE LOCATED AT CENTERLINE OF DOOR LEAF, WHERE OCCURS IN CLOSED POSITION, U.O.N.
- PROVIDE TRANSITION STRIPS IN LOCATION WHERE CHANGE IN FLOORING OCCURS.
- PAINTED HOLLOW METAL DOOR AND FRAMES TO MATCH ADJACENT WALL PAINT COLOR, U.O.N.
- ALL CERAMIC FLOOR TILE SHALL HAVE A 1'-0" BORDER AROUND PERIMETER OF ROOM PER SMCCCD'S STANDARDS TYP. TILE SIZE SHALL BE 2'X2', U.O.N.

**SYMBOLS LEGEND**

ROOM NAME AND NUMBER	Name	ACCENT PAINT COLOR, TILE FINISH, SPECIAL FINISH	EXTENT OF FINISH
FINISH IDENTIFIER	NUMBER	F   B   W   C   WT	
FLOOR FIN.			
BASE FIN.			
WALL FIN.			
CEILING FIN.			
WINDOW TREATMENT			

  

LINOLEUM	CARPET	CERAMIC TILE	ALTRO MAXIS SAFETY FLOORING SHEET	SEALED CONCRETE
----------	--------	--------------	-----------------------------------	-----------------

**LEGEND**

FLOOR FINISH	FLOOR FINISH	BASE FINISH	WALL FINISH	WALL FINISH	CEILING FINISH	WINDOW TREATMENT
0 SEE LINOLEUM FLOOR PATTERN SHEETS	13 EFM-ENTRANCE FLOOR MAT	A RB-1 RUBBER BASE	1 PT-1 PAINT, SEMI GLOSS	13 CT-2 CERAMIC TILE WITH BUILT UP BASE, PT-1 ABOVE TILE TO B.O. CEILING	A NOT USED	1 RSW-1 MANUAL
1 RFS-1 LINOLEUM	14 RFS-7 SAFETY FLOOR	B WOOD BASE PER 19A/910	2 PT-2 PAINT, EGGSHELL	14 PT-1 TYP WITH FRP-1 4'X8' FIBERGLASS REINFORCED PANELS AT MOP SINK CORNER	B ACP-2 ACOUSTICAL PANEL CEILING	2 DOUBLE SHADE RSW-1 AND RSW-2
2 RFS-2 LINOLEUM	15 CP-2 CARPET, ROLL		3 PT-3 PAINT, EGGSHELL	* WP-1 RIGID VINYL WAINSCOT & CHAIR RAIL SEE ELEVATIONS	C GYPSUM BOARD-PT-1	3 HLB-1
3 RFS-3 LINOLEUM	16 RST-1 RUBBER STAIR TREAD		4 PT-4 PAINT, EGGSHELL	* AWP-1 ACOUSTICAL WALL PANEL SEE ELEVATIONS	D GYPSUM BOARD-PT-2	4 RSW-1 MOTORIZED
4 RFS-4 LINOLEUM	17 PRECAST CONCRETE STAIRS		5 PT-5 PAINT, EGGSHELL	* WG-1 WALL GUARD CHAIR RAIL	E EXPOSED	
5 RFS-5 SAFETY FLOOR	18 RFS-5 SAFETY FLOOR/LINOLEUM SEE FLOOR PATTERN SHEET		6 PT-6 PAINT, EGGSHELL			
6 RFS-6 SAFETY FLOOR	* ALL ELEVATOR CABS FLOORS SHALL RECEIVE LINOLEUM COLOR: NORTHERN LIGHTS		7 PT-7 PAINT, EGGSHELL			
7 CPT-1 CARPET TILE			8 GT-1 GLASS TILE			
8 CPT-2 CARPET TILE			9 PCT-1 PORCELAIN TILE			
9 CPT-3 CARPET TILE			10 NOT USED			
10 CP-1 CARPET, ROLL			11 NOT USED			
11 CT-1 CERAMIC TILE WITH TILE BORDER			12 4' X 8' PLYWOOD, 8" HEIGHT TYP ON GYPSUM BOARD FINISH PT-2 VERIFY LOCATIONS			
12 COATED CONCRETE-PEDA-GARD M						

All drawings and written material appearing herein constitute original and unpublished work of the Architect/Engineer and may not be duplicated, used or disclosed without consent of Architect/Engineer.  
If this drawing is not 30"x42" then the drawing has been revised from its original size. Noted scales must be adjusted. This line should be equal to one inch.