SKYLINE COLLEGE
TCOM CLASSROOM RENOVATION BUILDING 2

THE INFORMATION SHOWN IS SOLELY TO ASSIST CONTRACTOR IN ESTIMATING ELECTRICAL DEMOLITION WORK. THIS INFORMATION IS OBTAINED FROM AVAILABLE

GENERAL NOTES

REMOVED PER CEC.

SHEET NOTES

DRAWINGS/RECORDS AND SHALL NOT BE RELIED UPON FOR CONSTRUCTION PURPOSES.

2. ALL LIGHT FIXTURES AND RECEPTACLES SHALL BE REPLACED U.O.N. CONDUITS/RACEWAYS EMBEDDED INTO WALLS, THROUGH EXTERIOR WALLS, AND THROUGH STRUCTURES SHALL BE PROPERLY SEALED WITH APPROPRIATE CAULKING MATERIALS.

OTHER CONDUITS/RACEWAYS WHICH REMAIN EMBEDDED MAY BE CAPPED AND ABANDONED IN PLACE AND TAGGED AS ABANDONED. HOWEVER, ALL WRING SHALL BE

3. CONTRACTOR MAY REUSE (E) CONDUIT/RACEWAY SYSTEMS FOR NEW WORK WHERE POSSIBLE.

4. REROUTE EXISTING RACEWAYS AND DEVICES LOCATED WITHIN WALLS SLATED FOR DEMOLITION IF REQUIRED TO REMAIN.


RELOCATE (E) FIRE ALARM PULLSTATION AND HORN TO (N) LOCATION SHOWN BY ARROW.




owner
SAN MATEO COUNTY
3401 CSM DRUVE
SAN MATEO CA 94402

architect
STEINBERG ARCHITECTS
60 Pierce Avenue
San Jose CA 95110








02.02.07 DSA SUBMITTAL

DSA BACKCHECK

v. date issu



STEINBERGARCHITECTSproject no:06044date:03/15/07drawn by:VBchecked by:DLscale:1/4"=1'-0"04"8"

ELECTRICAL DEMOLITION PLAN

E1.01